



# MONTECITO WATER DISTRICT

160 East Via Verde, Suite 240  
San Dimas, California, 91773  
PHONE: (909) 305-2930 FAX: (909) 305-2959



www.tetrattech.com

## RESERVOIR SEISMIC RETROFIT AND REPLACEMENT PROJECT FOR PARK LANE RESERVOIR



### PROJECT LOCATION:

PARK LANE NEAR EAST MOUNTAIN DRIVE  
MONTECITO, CALIFORNIA  
34.447663, -119.617445

### CLIENT INFORMATION:

MONTECITO WATER DISTRICT  
583 San Ysidro Rd  
Montecito, CA 93108

### Tt PROJECT No.:

200-106490-21001

### CLIENT PROJECT No.:

P132

### PROJECT DESCRIPTION / NOTES:

REPLACEMENT OF THE EXISTING RESERVOIR STRUCTURE WITH A NEW  
REINFORCED CONCRETE STRUCTURE CONSTRUCTED WITHIN THE FOOTPRINT  
OF THE EXISTING RESERVOIR


### ISSUED:

06/23/2021: 60 PERCENT DESIGN REVIEW  
08/12/2021: 90 PERCENT DESIGN REVIEW  
10/15/2021: 100 PERCENT DESIGN REVIEW  
4/18/2025: FINAL SUBMITTAL


### SHEET INDEX

SHEET NO.	DESCRIPTION
COVER	COVER SHEET
C-101	SITE PLAN
C-102	PIPING PLAN
C-501	CIVIL DETAILS
C-502	CIVIL DETAILS
C-503	CIVIL DETAILS
S-001	GENERAL STRUCTURAL NOTES
S-002	SPECIAL INSPECTIONS AND STRUCTURAL OBSERVATIONS
S-101	DEMOLITION PLANS
S-102	DEMOLITION SECTIONS
S-103	FOUNDATION PLAN
S-104	ROOF DECK PLAN
S-301	PARTIAL RESERVOIR SECTION
S-302	COLUMN SECTION
S-303	ROOF SLAB CROSS SECTION
S-501	STRUCTURAL DETAILS 1
S-502	STRUCTURAL DETAILS 2
S-503	STRUCTURAL DETAILS 3
S-504	STRUCTURAL DETAILS 4


### LOCATION MAP:



### VICINITY MAP:


















4/18/2025 2:28:01 PM - N:\LOCAL\PROJECTS\IRVINE\106490-2\1001\CAD\DWG\DETAILS\LANE\C-502-CVILDETAILS.DWG - HUTCHINS, ERIC




1 12" OUTLET PIPE CONNECTION DETAIL  
SCALE: 1/2"=1'-0"




2 4" INLET PIPE CONNECTION DETAIL  
SCALE: 1/2"=1'-0"




3 4" INLET PIPE RISER (WEST) DETAIL  
SCALE: 1/4"=1'-0"



4 4" INLET PIPE RISER (NORTH) DETAIL  
SCALE: 1/4"=1'-0"



5 RESERVOIR WALL PENETRATION DETAIL (SUBMERGED)  
SCALE: N.T.S.



**TETRA TECH**

www.tetratech.com

160 East Via Verde, Suite 240  
San Dimas, California, 91773  
Phone: (909) 305-2930 Fax: (909) 305-2959



4/18/25



MARK	DATE	DESCRIPTION	BY


MONTECITO WATER DISTRICT  
RESERVOIR SEISMIC RETROFIT AND REPLACEMENT  
PROJECT FOR PARK LANE RESERVOIR  
CIVIL DETAILS

Project No.: 200-106490-21001  
Designed By: AML  
Drawn By: AS  
Checked By: KRB


**C-502**

Bar Measures 1 inch






1 INLET PIPE SUPPORT DETAIL  
— SCALE: 1"=1'-0"




2 MUD VALVE/FLOOR DRAIN DETAIL  
- SCALE: 1/4"=1'-0"




### 3 PIPE TRENCHING DETAIL


SCALE: N.T.S.



4 CUT AND PLUG DETAIL  
— SCALE: N.T.S.



## 5 ADJUSTABLE PIPE SUPPORT WITH CONCRETE BASE



6  
- RESERVOIR WALL  
PENETRATION DETAIL (ABOVE WATER LINE)  
SCALE: N.T.S.

[illegible]



4/18/2025 2:28:43 PM - N:\T\LOCAL\PROJECTS\IRVINE\106490\200-106490-2\1001\CAD\SHEETFILES\PARK LANE\S-001-GENNOTES.DWG - HUTCHINS, ERIC

GENERAL STRUCTURAL NOTES  
THESE NOTES SHALL APPLY UNLESS SHOWN/INDICATED OTHERWISE ELSEWHERE IN THE STRUCTURAL DRAWINGS.

GENERAL

- ALL MATERIALS AND CONSTRUCTION SHALL CONFORM TO THE 2019 CALIFORNIA BUILDING CODE (C.B.C.) BASED UPON THE 2018 EDITION OF THE INTERNATIONAL BUILDING CODE (I.B.C.). THE MATERIALS AND CONSTRUCTION SHALL CONFORM WITH ACI 350-06.
- CONTRACTOR SHALL VERIFY ALL EXISTING CONDITIONS AND DIMENSIONS BEFORE STARTING WORK. DIMENSIONS OF (E) CONSTRUCTION WHERE SHOWN ON THESE DRAWINGS ARE NOMINAL AND SHOULD BE FIELD VERIFIED. SHOULD CONDITIONS EXIST WHICH ARE CONTRARY TO THOSE SHOWN ON PLANS, THE ENGINEER SHALL BE NOTIFIED IN WRITING BEFORE PROCEEDING WITH WORK.
- UNLESS DETAILED, SPECIFIED, OR INDICATED OTHERWISE, CONSTRUCTION SHALL BE AS INDICATED IN THE APPLICABLE TYPICAL DETAILS AND THESE GENERAL NOTES. TYPICAL DETAILS ARE MEANT TO APPLY EVEN THOUGH NOT REFERENCED AT SPECIFIC LOCATIONS ON DRAWINGS WHERE THEY OCCUR.
- THE CONTRACT DRAWINGS AND SPECIFICATIONS REPRESENT THE FINISHED STRUCTURE. THEY DO NOT INDICATE THE METHOD OF CONSTRUCTION. THE CONTRACTOR SHALL PROVIDE ALL MEASURES NECESSARY TO PROTECT THE STRUCTURE, WORKERS AND PEDESTRIANS DURING CONSTRUCTION. SUCH MEASURES SHALL INCLUDE, BUT NOT BE LIMITED TO BRACING, SHORING FOR LOADS DUE TO CONSTRUCTION EQUIPMENT, TEMPORARY STRUCTURES, AND PARTIALLY COMPLETED WORK, ETC. OBSERVATION VISITS TO THE SITE BY THE ENGINEER SHALL NOT BE CONSIDERED AS INSPECTION OF SUCH ITEMS.
- DIMENSIONS SHALL TAKE PRECEDENCE OVER SCALES SHOWN ON DRAWINGS.
- ALL WORK SHALL CONFORM TO THE PLANS AND SPECIFICATIONS IN ALL RESPECTS AND SHALL BE SUBJECT TO APPROVAL BY THE ENGINEER.
- ASSUMED DESIGN SOIL BEARING VALUE IS 3000 PSF PER TABLE 1806.3 OF THE 2019 CBC, FOR SANDY GRAVEL OR SAND (CLASSIFICATION GW OR GP). THIS SOIL BEARING ASSUMPTION SHALL BE VERIFIED AFTER THE EXCAVATION IS COMPLETE.
- CONTRACTOR SHALL VERIFY LOCATION OF ALL SITE UTILITIES PRIOR TO STARTING WORK, BOTH ABOVE GROUND AND BELOW GROUND, WHICH MAY BE IMPACTED BY THE WORK SHOWN ON THESE DRAWINGS. ANY CONFLICTS SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER.
- ALL ITEMS SHOWN ON THESE PLANS ARE NEW UNLESS NOTED (E), EXIST, OR EXISTING.

REINFORCING NOTES

- REINFORCEMENT FOR CONCRETE AND MASONRY SHALL BE DEFORMED BARS CONFORMING TO ASTM SPECIFICATION A615 (A706/A706M FOR WELDED REINFORCING). GRADE 60 STEEL SHALL BE USED.
- WIRE MESH, WHERE USED, SHALL CONFORM TO ASTM A185. LAP 12" WHERE SPLICED.
- ALL REINFORCEMENT, ANCHOR BOLTS, AND OTHER ANCHORAGES PLACED IN MASONRY AND CONCRETE SHALL BE ACCURATELY PLACED AND POSITIVELY SECURED AND SUPPORTED BY CONCRETE BLOCKS, METAL CHAIRS, SPACERS, OR METAL HANGERS, AND SHALL BE IN POSITION BEFORE CONCRETE PLACING OR GROUTING IS BEGUN. DETAILING AND PLACING OF BARS SHALL CONFORM TO THE A.C.I. MANUAL OF STANDARD PRACTICES.
- BARS SPECIFIED AS "CONTINUOUS" SHALL EXTEND THE FULL LENGTH OF THE MEMBER CONTAINING THEM AND MAY BE SPLICED (UNLESS NOTED OR SHOWN WITHOUT SPLICES ON THE PLANS). IN CONCRETE, PROVIDE LAPS PER DETAIL 2 ON SHEET S-501. STAGGER ALL SPLICES.
- DOWELS SHALL BE PROVIDED AT ALL POUR JOINTS AND SHALL BE THE SAME SIZE AND SPACING AS REINFORCING DIRECTLY BEYOND POUR JOINTS.
- WELDING OF REINFORCING STEEL, METAL INSERTS AND CONNECTIONS IN REINFORCED CONCRETE OR MASONRY CONSTRUCTION SHALL CONFORM TO ANSI/AWS D1.4-11. USE LOW HYDROGEN E-70 SERIES ELECTRODES FOR WELDING OF REINFORCING BARS. CONTINUOUS INSPECTION IS REQUIRED OF ALL FIELD WELDING IN ACCORDANCE WITH C.B.C. CHAPTER 17.

CONCRETE NOTES

- ALL CONCRETE FOR THE RESERVIR STRUCTURE SHALL HAVE A MINIMUM ULTIMATE COMPRESSIVE STRENGTH OF 4500 PSI AT 28 DAYS. REFER TO THE PROJECT SPECIFICATIONS FOR THE REQUIREMENTS FOR OTHER CONCRETE. AGGREGATES SHALL CONFORM TO ASTM C33.
- CEMENT FOR CONCRETE SHALL BE TYPE V PORTLAND CEMENT CONFORMING TO A.S.T.M. C150.
- CONCRETE COVER FOR REINFORCING BARS SHALL BE:  
CAST AGAINST AND PERMANENTLY EXPOSED TO EARTH = 3"  
EXPOSED TO EARTH OR WEATHER, NO. 6 THROUGH NO. 18 BARS = 2"  
NO. 5 BARS, W#1 OR D#1 WIRE, AND SMALLER = 1 1/2"  
NOT EXPOSED TO WEATHER OR IN CONTACT WITH THE GROUND:  
SLABS, WALLS, JOISTS: NO. 14 AND NO. 18 BARS = 1 1/2"  
NO. 11 BARS AND SMALLER = 3/4"  
BEAMS, COLUMNS: PRIMARY REINFORCEMENT, TIES, STIRRUPS, SPIRALS = 1 1/2"
- DRYPACK SHALL BE 1 PART CEMENT AND 3 PARTS SAND (BY VOLUME).
- NO PIPES OR DUCTS SHALL BE PLACED IN STRUCTURAL CONCRETE UNLESS SPECIFICALLY DETAILED. SEE MECHANICAL AND/OR ELECTRICAL DRAWINGS FOR LOCATION OF SLEEVES THROUGH WALLS AND FLOORS.
- THE LOCATION OF ALL CONSTRUCTION JOINTS NOT SPECIFICALLY NOTED OR SHOWN SHALL BE APPROVED BY THE STRUCTURAL ENGINEER.
- "ROUGHENED SURFACES", WHERE SPECIFIED ON THE DRAWINGS, SHALL BE MECHANICALLY ROUGHENED SUCH THAT A 1/4" AMPLITUDE (±) IS ACHIEVED BETWEEN HIGH AND LOW SPOTS OF THE ROUGHENED SURFACE. THE SURFACE SHALL BE CLEAN AND FREE OF LAITANCE
- BOTH FACES OF CONCRETE WALLS, EDGES OF CONCRETE FOUNDATIONS, AND OTHER FORMED CONCRETE SURFACES WHERE THE CONCRETE COVER IS SPECIFIED AS LESS THAN 3 INCHES, SHALL BE PLACED AGAINST FORMWORK WHICH COMPLIES WITH THE PROJECT SPECIFICATIONS. CONCRETE FOR THESE ELEMENTS SHALL NOT BE CAST AGAINST EARTH.

STEEL NOTES

- ALL WIDE FLANGE MEMBERS SHALL BE IN ACCORDANCE WITH ASTM A-992. ALL OTHER STRUCTURAL AND MISCELLANEOUS STEEL SHALL BE ASTM A36 UNLESS NOTED OTHERWISE. STRUCTURAL STEEL SHALL BE FABRICATED AND ERECTED IN ACCORDANCE WITH THE AISC SPECIFICATION FOR THE DESIGN, FABRICATION AND ERECTION OF STRUCTURAL STEEL FOR BUILDINGS. SPECIAL INSPECTION SHALL BE PROVIDED FOR ALL STRUCTURAL STEEL IN ACCORDANCE WITH CBC SECTION 1705.2.1, UNLESS FABRICATION IS PERFORMED ON THE PREMISES OF A FABRICATOR REGISTERED AND APPROVED TO PERFORM SUCH WORK WITHOUT SPECIAL INSPECTION. IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS AND SECTION 1704.2.5.2 OF THE 2019 CBC. AT THE COMPLETION OF FABRICATION, THE APPROVED FABRICATOR SHALL SUBMIT A CERTIFICATE OF COMPLIANCE TO THE ENGINEER STATING THAT THE WORK WAS PERFORMED IN ACCORDANCE WITH THE CONTRACT DOCUMENTS.
- STEEL TUBES SHALL CONFORM TO A.S.T.M. A500, GRADE B OR BETTER, UNLESS NOTED OTHERWISE.
- STEEL PIPES SHALL CONFORM TO ASTM A53, GRADE B.
- BOLTS SHALL CONFORM TO ASTM A307 OR BETTER, UNLESS NOTED OTHERWISE.
- HOLES FOR BOLTS IN STEEL SHALL BE OF SAME DIAMETER AS BOLT +1/16" MAXIMUM.
- ALL WELDING SHALL BE SHIELDED ARC TYPE AND SHALL BE PERFORMED BY A CERTIFIED WELDER IN A FABRICATION SHOP REGISTERED AND APPROVED IN ACCORDANCE WITH NOTE 1 ABOVE. CONTINUOUS INSPECTION IS REQUIRED OF ALL FIELD WELDING IN ACCORDANCE WITH AWS D1.1.
- NO STRUCTURAL STEEL MEMBER SHALL BE CUT FOR PIPES, DUCTS, ETC. UNLESS SPECIFICALLY DETAILED AND APPROVED BY STRUCTURAL ENGINEER.
- STAINLESS STEEL SHALL CONFORM TO A.S.T.M. A276/A.I.S.I. 316. STAINLESS STEEL BOLTS SHALL CONFORM TO A.S.T.M. F593. STAINLESS STEEL NUTS SHALL CONFORM TO A.S.T.M. F594.
- WELDING OF STAINLESS STEEL SHALL CONFORM TO STRUCTURAL WELDING CODE - STAINLESS STEEL, ANSI/AWS D1.6-07.
- WHERE SPECIFIED, USE OF HIGH-STRENGTH BOLTS SHALL CONFORM TO THE PROVISIONS OF THE "SPECIFICATION FOR STRUCTURAL JOINTS USING A.S.T.M. A325 OR A490 BOLTS" APPROVED BY THE RESEARCH COUNCIL ON STRUCTURAL CONNECTIONS OF THE ENGINEERING FOUNDATION (RCSC). SPECIAL INSPECTION OF HIGH-STRENGTH BOLT CONNECTIONS IS REQUIRED.
- ALL NON-STAINLESS STEEL THAT IS NOT SCHEDULED TO BE PAINTED, SHALL BE HOT-DIP GALVANIZED IN ACCORDANCE WITH ASTM A123 OR A153, AS APPLICABLE. REPAIR OF DAMAGED GALVANIZED COATING SHALL BE IN ACCORDANCE WITH ASTM A780. ALL OTHER NON-STAINLESS STEEL SHALL BE COATED WITH TWO COATS OF SHOP APPLIED PRIMER THAT IS COMPATIBLE WITH THE TOP COATS. REFER TO THE PROJECT SPECIFICATIONS.
- WELDING EQUIPMENT SHALL BE CHECKED PRIOR TO WELDING AS REQUIRED BY AISC 360-16 TABLE N5.4-1.
- PRE-INSTALLATION VERIFICATION TESTING BY INSTALLATION PERSONNEL OBSERVED AND DOCUMENTED FOR FASTENER ASSEMBLIES AND METHODS USED SHALL BE PERFORMED AS REQUIRED BY AISC 360-16 TABLE N5.6-1

ADHESIVE ANCHORS (SIMPSON)

- ADHESIVE ANCHORS SHALL BE "SET-3G" ADHESIVE ANCHORS, MANUFACTURED BY SIMPSON STRONG-TIE.
- ANCHORS SHALL BE INSTALLED IN ACCORDANCE WITH I.C.C. EVALUATION REPORT No. 4057.
- SPECIAL INSPECTION PER CHAPTER 17 OF THE CALIFORNIA BUILDING CODE SHALL BE PROVIDED DURING ANCHOR INSTALLATION.
- AN ALTERNATIVE ADHESIVE ANCHOR PRODUCT MAY BE SUBMITTED TO THE ENGINEER FOR APPROVAL, PROVIDED THAT IT HAS A CURRENT I.C.C. EVALUATION REPORT APPROVAL.
- ALL ABANDONED HOLES SHALL BE FILLED WITH A DRYPACK GROUT. A MINIMUM 28-DAY COMPRESSIVE STRENGTH OF 5,000 PSI. THE FILLED HOLE(S) SHALL BE PREPARED AND CLEANED AS REQUIRED BY THE GROUT MANUFACTURER.
- LOCATE EXISTING REINFORCING USING A NON-DESTRUCTIVE METHOD (PACHOMETER OR OTHER), PRIOR TO STEEL FABRICATION OF THE AFFECTED COMPONENTS AND PRIOR TO DRILLING HOLES FOR ANCHORS. MAINTAIN A MINIMUM CLEARANCE OF 1" BETWEEN THE REINFORCEMENT AND THE ANCHOR. NOTIFY ENGINEER IF ADHESIVE ANCHORS CANNOT BE INSTALLED DUE TO REBAR INTERFERENCE(S) SO STRUCTURAL STEEL DETAILING SHOWN HEREON CAN BE MODIFIED TO ACCOMMODATE.

CEMENT SLURRY BACKFILL

- CEMENT SLURRY MAY BE USED IN LIEU OF COMPACTED SOIL BACKFILL ONLY WHERE INDICATED ON THE PLANS.
- CEMENT SLURRY SHALL CONSIST OF TYPE II CEMENT IN ACCORDANCE WITH A.S.T.M. C-150, WATER AND AGGREGATE. AGGREGATE SHALL BE EITHER EXCAVATION MATERIAL FREE OF ORGANIC MATERIAL OR COMMERCIAL QUALITY CONCRETE SAND CONFORMING TO A.S.T.M. C-33 FOR FINE AGGREGATE. IF EXCAVATED MATERIAL IS USED FOR THE SLURRY AGGREGATE, IT SHALL MEET THE FOLLOWING GRADING REQUIREMENTS:

SIEVE SIZE	PCT. PASSING
1"	80 - 100
3/4"	60 - 100
3/8"	50 - 100
No. 4	40 - 80
No. 100	10 - 40
- THE MINIMUM AMOUNT OF CEMENT SHALL NOT BE LESS THAN 2 SACKS (188 LBS.) PER CUBIC YARD OF SLURRY. ENOUGH WATER SHALL BE ADDED TO PRODUCE A FLUID, WORKABLE MIX THAT WILL FLOW AND CAN BE PUMPED WITHOUT SEGREGATION OF THE AGGREGATE WHILE BEING PLACED.
- THE CEMENT SLURRY SHALL BE PLACED WITHIN ONE HOUR OF BEING MIXED.
- A MINIMUM OF 4 HOURS SHALL ELAPSE PRIOR TO THE PLACEMENT OF BACKFILL ON THE CEMENT SLURRY.

DESIGN CRITERIA:

DESIGN CODES AND REFERENCES:  
-CALIFORNIA BUILDING CODE, 2019 EDITION  
-ASCE/SEI 7-16 MINIMUM DESIGN LOADS FOR BUILDINGS & OTHER STRUCTURES  
-ACI 318-14 BUILDING CODE REQUIREMENTS FOR STRUCTURAL CONCRETE  
-ACI 350 CODE REQUIREMENTS FOR ENVIRONMENTAL ENGINEERING CONCRETE STRUCTURES  
-ACI 350.3 SEISMIC DESIGN OF LIQUID CONTAINING CONCRETE STRUCTURES

ROOF LOADING:  
DEAD LOAD = 5 PSF (SOLAR PANEL ALLOWANCE)  
SELF WEIGHT OF CONCRETE DEAD LOAD = 113 PSF (9 INCH CONCRETE SLAB)  
LIVE LOAD = 100 PSF (ROOF SLAB DESIGN ONLY)  
LIVE LOAD = 40 PSF (COLUMN AND WALL DESIGN ONLY)

SEISMIC DESIGN PARAMETERS:  
ANALYSIS PROCEDURE USED: EQUIVALENT LATERAL FORCE PROCEDURE  
LOCATION: LAT. 34.447750 N, LONG. 119.617518 W  
RISK CATEGORY: IV  
SITE CLASS: D (DEFAULT)

Ss = 2.089	Fa = 1.200	SDS = 1.671
Ss = 2.089	Fv = 1.700	SD1 = 0.773
Ri = 2.00	Sai = 1.671	Cs = 1.253
Rc = 1.00	Sac = 0.023	Cs = 0.034
IE = 1.50		

GEOTECHNICAL PARAMETERS:

BASED GEOTECHNICAL DESIGN ON TABLE 1806.2 IN CBC 2019 CLASS 3  
ALLOWABLE BEARING PRESSURE = 3000 PSF  
(INCREASED BY ONE-THIRD FOR SEISMIC LOADING CONDITION)

SOIL LATERAL LOAD  
AT-REST PRESSURE = 60 PSF/FT (SANDY / GRAVELY SOIL PER ASCE 7-16 TABLE 3.2-1 FOOTNOTE B.)  
SOIL SEISMIC PRESSURE = 30.5 PSF/FT (ASSUMED - UNIFORMLY DISTRIBUTED LOAD)



**TETRA TECH**  
www.tetrattech.com  
160 East Via Verde, Suite 240  
San Dimas, California, 91773  
Phone: (909) 305-2930 Fax: (909) 305-2959



REGISTERED PROFESSIONAL ENGINEER  
ERIC YUEN  
No. 81177  
STRUCTURAL  
STATE OF CALIFORNIA  
4/18/25



MARK	DATE	DESCRIPTION	BY

MONTECITO WATER DISTRICT  
RESERVOIR SEISMIC RETROFIT AND REPLACEMENT  
PROJECT FOR PARK LANE RESERVOIR

GENERAL STRUCTURAL NOTES


Project No.: 200-106490-21001  
Designed By: VMR  
Drawn By: E.J.H.  
Checked By: VMR

S-001



4/18/2025 2:29:01 PM - N:\T\LOCAL\PROJECTS\IRVINE\106490-2\1001\CAD\SHEETFILES\PARK LANE\02-SPEC\INSPEC.DWG - HUTCHINS, ERIC


F	SPECIAL INSPECTIONS REQUIRED			STEEL CONSTRUCTION (STRUCTURAL STEEL):			STEEL CONSTRUCTION (STRUCTURAL STEEL CONT.):			STRUCTURAL OBSERVATION		
	SPECIAL INSPECTIONS REQUIRED FOR THIS PROJECT SHALL BE PERFORMED IN ACCORDANCE WITH C.B.C. CHAPTER 17. SPECIAL INSPECTIONS SHALL BE PERFORMED BY AN APPROVED INSPECTION AGENCY U.N.O., EMPLOYED BY THE OWNER.			R - INSPECT THESE ITEMS ON A <u>RANDOM</u> BASIS. OPERATIONS NEED NOT BE DELAYED PENDING THESE INSPECTIONS C - INSPECT THESE ITEMS ON A <u>CONTINUOUS</u> BASIS			C R N/A			THE STRUCTURAL ENGINEER, OR ANOTHER ENGINEER DESIGNATED BY THE STRUCTURAL ENGINEER SHALL BE RETAINED BY THE OWNER TO PERFORM STRUCTURAL OBSERVATION AS REQUIRED BY C.B.C. CHAPTER 17. STRUCTURAL OBSERVATION SHALL BE PROVIDED DURING THE STAGES OF CONSTRUCTION LISTED BELOW. IT SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO PROVIDE AT LEAST 48 HOURS ADVANCE NOTICE TO THE STRUCTURAL ENGINEER WHEN HIS WORK IS READY FOR STRUCTURAL OBSERVATION FOR EACH OF THESE STAGES.		
T	THE SPECIAL INSPECTOR SHALL BE CERTIFIED BY THE INTERNATIONAL CODE COUNCIL (I.C.C.) TO PERFORM INSPECTION FOR THE PARTICULAR TYPE OF CONSTRUCTION OR OPERATION REQUIRING SPECIAL INSPECTION PRIOR TO THE COMPLETION OF THAT PHASE OF THE WORK.			C R N/A			4. INSPECTION TASKS PRIOR TO BOLTING A. MANUFACTURER'S CERTIFICATION AVAILABLE FOR FASTENER MATERIALS B. FASTENERS MARKED IN ACCORDANCE WITH ASTM REQUIREMENTS C. CORRECT FASTENERS SELECTED FOR THE JOINT DETAIL (GRADE, TYPE, BOLT LENGTH IF THREADS ARE TO BE EXCLUDED FORM SHEAR PLANE) D. CORRECT BOLTING PROCEDURE SELECTED FOR JOINT DETAIL E. CONNECTING ELEMENTS, INCLUDING THE APPROPRIATE FAYING SURFACE CONDITION AND HOLE PREPARATION, IF SPECIFIED, MEET APPLICABLE REQUIREMENTS F. PRE-INSTALLATION VERIFICATION TESTING BY INSTALLATION PERSONNEL OBSERVED AND DOCUMENTED FOR FASTENER ASSEMBLIES AND METHODS USED G. PROTECTED STORAGE PROVIDED FOR BOLTS, NUTS, WASHERS AND OTHER FASTENER COMPONENTS			1. CONCRETE: REINFORCING STEEL AND EMBEDDED STRUCTURAL ANCHORAGES PRIOR TO PLACEMENT OF CONCRETE FOR THE FOLLOWING:  A. FOUNDATIONS B. SLABS-ON-GRADE (EXCEPT SITE PAVING AND FLATWORK) C. WALLS D. STRUCTURAL FLOOR SLABS AND BEAMS NOT SUPPORTED ON-GRADE E. ROOF SLABS AND BEAMS		
	THE SPECIAL INSPECTOR SHALL FURNISH INSPECTION REPORTS TO THE BUILDING OFFICIAL AND/OR THE ENGINEER. ALL DISCREPANCIES SHALL BE BROUGHT TO THE IMMEDIATE ATTENTION OF THE CONTRACTOR FOR CORRECTION, THEN, IF UNCORRECTED, TO THE STRUCTURAL ENGINEER AND TO THE BUILDING OFFICIAL.			1. INSPECTION TASKS PRIOR TO WELDING A. WELDER QUALIFICATION RECORDS AND CONTINUITY RECORDS B. WELDING PROCEDURE SPECIFICATIONS (WPSs) AVAILABLE C. MANUFACTURERS CERTIFICATIONS FOR WELDING CONSUMABLES AVAILABLE D. MATERIAL IDENTIFICATION (TYPE/GRADE) E. WELDER IDENTIFICATION SYSTEM F. FIT-UP OF GROOVE WELDS (INCLUDING JOINT GEOMETRY) - JOINT PREPARATION - DIMENSIONS (ALIGNMENT, ROOT OPENING, ROOT FACE, BEVEL) - CLEANLINESS (CONDITION OF STEEL SURFACES) - TACKING (TACK WELD QUALITY AND LOCATION) - BACKING TYPE AND FIT (IF APPLICABLE) G. FIT-UP OF CJP GROOVE WELDS OF HSS T-, Y- AND K- JOINTS WITHOUT BACKING (INCLUDING JOINT GEOMETRY) - JOINT PREPARATIONS - DIMENSIONS (ALIGNMENT, ROOT OPENING, ROOT FACE, BEVEL) - CLEANLINESS (CONDITION OF STEEL SURFACES) - TACKING (TACK WELD QUALITY AND LOCATION) H. CONFIGURATION AND FINISH OF ACCESS HOLES I. FIT-UP OF FILLET WELDS - DIMENSIONS (ALIGNMENT, GAPS AT ROOT) - CLEANLINESS (CONDITION OF STEEL SURFACES) - TACKING (TACK WELD QUALITY AND LOCATION) 2. INSPECTION TASKS DURING WELDING A. CONTROL AND HANDLING OF WELDING CONSUMABLES - PACKAGING - EXPOSURE CONTROL B. NO WELDING OVER CRACKED TACK WELDS C. ENVIRONMENTAL CONDITIONS - WIND SPEED WITHIN LIMITS - PRECIPITATION AND TEMPERATURE D. WPS FOLLOWED: - SETTINGS ON WELDING EQUIPMENT - TRAVEL SPEED - SELECTED WELDING MATERIALS - SHIELDING GAS TYPE/FLOW RATE - PREHEAT APPLIED - INTERPASS TEMPERATURE MAINTAINED (MIN./MAX.) - PROPER POSITION (F, V, H, OH) E. WELDING TECHNIQUES - INTERPASS AND FINAL CLEANING - EACH PASS WITHIN PROFILE LIMITATIONS - EACH PASS MEETS QUALITY REQUIREMENTS F. PLACEMENT AND INSTALLATION OF STEEL HEADED STUD ANCHORS			5. INSPECTION TASKS DURING BOLTING A. FASTENER ASSEMBLIES, OF SUITABLE CONDITION, PLACED IN ALL HOLES AND WASHERS ARE POSITIONED AS REQUIRED B. JOINT BROUGHT TO THE SNUG-TIGHT CONDITION PRIOR TO THE PRETENSIONING OPERATION C. FASTENER COMPONENT NOT TURNED BY THE WRENCH PREVENTED FOR ROTATING D. FASTENERS ARE PRETENSIONED IN ACCORDANCE WITH THE RCSC SPECIFICATION, PROGRESSING SYSTEMATICALLY FROM THE MOST RIGID POINT TOWARD THE FREE EDGES 6. INSPECTION TASKS AFTER BOLTING A. DOCUMENT ACCEPTANCE OR REJECTION OF BOLTED CONECTIONS 7. INSPECTION OF STEEL ELEMENTS OF COMPOSITE CONSTRUCTION PRIOR TO CONCRETE PLACEMENT A. PLACEMENT AND INSTALLATION OF STEEL DECK B. PLACEMENT AND INSTALLATION OF STEEL HEADED STUD ANCHORS C. DOCUMENT ACCEPTANCE OR REJECTION OF STEEL ELEMENTS			2. STRUCTURAL STEEL: A. ERECTED COLUMN, BEAMS AND GIRDERS, PRIOR TO INSTALLATION OF ROOF AND FLOOR JOISTS, TRUSSES AND DECKING		
E	IT SHALL BE THE CONTRACTOR'S SOLE RESPONSIBILITY TO PROVIDE AT LEAST 48 HOURS ADVANCE NOTICE TO THE OWNER/OWNER'S REPRESENTATIVE WHEN HIS WORK IS READY FOR ANY REQUIRED SPECIAL INSPECTIONS.			CONT PERIODIC N/A			ADHESIVE ANCHORS: 1. VERIFY ANCHOR TYPE: 2. VERIFY ADHESIVE IDENTIFICATION AND EXPIRATION DATE 3. VERIFY ANCHOR DIMENSIONS: 4. VERIFY CONCRETE TYPE: 5. VERIFY CONCRETE COMPRESSIVE STRENGTH: 6. VERIFY HOLE DRILLING METHOD: 7. VERIFY HOLE DIMENSIONS 8. VERIFY HOLE CLEANING PROCEDURES 9. VERIFY ANCHOR SPACING 10. VERIFY EDGE DISTANCES 11. VERIFY CONCRETE THICKNESS 12. VERIFY ANCHOR EMBEDMENT 13. VERIFY TIGHTENING TORQUE 14. VERIFY ADHERENCE TO THE MANUFACTURER'S PRINTED INSTALLATION INSTRUCTIONS			DEFERRED SUBMITTALS/CERTIFICATIONS SUBMITTALS REQUIRED (YES NO) 1. OFF-SITE FABRICATION: FABRICATORS SHALL BE CITY, COUNTY AND/OR C.B.C. APPROVED FABRICATORS. FABRICATORS  FOR ALL OFF-SITE FABRICATION OF THE ITEMS LISTED BELOW:  A. TRUSSES B. GLU-LAMINATED MEMBERS C. PRECAST CONCRETE D. STRUCTURAL STEEL (MILL REPORTS AND IDENTIFICATION OF STEEL, AFFIDAVIT OF COMPLIANCE) E. OTHER:  2. DEFERRED SUBMITTALS: SUBMITTAL DOCUMENTS FOR THE DEFERRED SUBMITTAL ITEMS LISTED BELOW SHALL BE DESIGNED BY A LICENSED PE OR SE AND SUBMITTED BY THE CONTRACTOR TO THE BUILDING DEPARTMENT/APPROVAL AGENCY AND STRUCTURAL ENGINEER FOR REVIEW AND APPROVAL. THE DEFERRED SUBMITTAL ITEMS SHALL NOT BE INSTALLED UNTIL THEIR DESIGN AND SUBMITTAL DOCUMENTS HAVE BEEN APPROVED BY THE BUILDING OFFICIAL.  A. PREFABRICATED TRUSSES B. PRECAST VAULTS C. OTHER: PRECAST CONC. PILES		
	SHOP INSPECTION OF STEEL CONSTRUCTION IS NOT REQUIRED WHEN THE WORK IS DONE ON THE PREMISES OF A FABRICATOR REGISTERED AND APPROVED TO PERFORM SUCH WORK WITHOUT SPECIAL INSPECTION. APPROVAL SHALL BE BASED UPON REVIEW OF THE FABRICATOR'S WRITTEN PROCEDURAL AND QUALITY CONTROL MANUALS AND PERIODIC AUDITING OF FABRICATION PRACTICES BY AN APPROVED SPECIAL INSPECTION AGENCY. AT COMPLETION OF FABRICATION, THE APPROVED FABRICATOR SHALL SUBMIT A CERTIFICATE OF COMPLIANCE TO THE BUILDING OFFICIAL STATING THAT THE WORK WAS PERFORMED IN ACCORDANCE WITH THE APPROVED CONSTRUCTION DOCUMENTS.			OWNER OR OWNER'S REPRESENTATIVE SHALL BE SYNONYMOUS WITH 'BUILDING OFFICIAL' IN THE FOREGOING IF THE PROJECT IS NOT UNDER THE JURISDICTION OF A BUILDING DEPARTMENT			THE SPECIAL INSPECTOR MUST VERIFY THE INITIAL INSTALLATIONS OF EACH TYPE AND SIZE OF ADHESIVE ANCHOR INSTALLED BY THE CONSTRUCTION PERSONNEL ON SITE. SUBSEQUENT INSTALLATIONS OF THE SAME ANCHOR TYPE AND SIZE BY THE SAME CONSTRUCTION PERSONNEL MAY BE PERMITTED, WITH THE APPROVAL OF THE ENGINEER AND THE SPECIAL INSPECTOR, TO BE PERFORMED IN THE ABSENCE OF THE SPECIAL INSPECTOR. ANY CHANGE IN THE ANCHOR PRODUCT BEING INSTALLED OR THE PERSONNEL PERFORMING THE INSTALLATION REQUIRES AN INITIAL INSPECTION. FOR ONGOING INSTALLATIONS OVER AN EXTENDED PERIOD, THE SPECIAL INSPECTOR MUST MAKE REGULAR INSPECTIONS TO CONFIRM CORRECT HANDLING AND INSTALLATION OF THE PRODUCT. THE SPECIAL INSPECTOR SHALL INFORM THE ENGINEER OF THE FREQUENCY OF THE PERIODIC ANCHOR INSPECTIONS. THE ENGINEER MAY REQUEST ADDITIONAL INSPECTIONS AT ANY TIME.					
D	CONTRACTOR RESPONSIBILITY EACH CONTRACTOR RESPONSIBLE FOR THE CONSTRUCTION OF A MAIN WIND- OR SEISMIC-FORCE-RESISTING SYSTEM, DESIGNATED SEISMIC SYSTEM OR A WIND- OR SEISMIC-RESISTING COMPONENT LISTED IN THE STATEMENT OF SPECIAL INSPECTIONS SHALL SUBMIT A WRITTEN STATEMENT OF RESPONSIBILITY TO THE BUILDING OFFICIAL AND THE OWNER PRIOR TO THE COMMENCEMENT OF WORK ON THE SYSTEM OR COMPONENT. THE CONTRACTOR'S STATEMENT OF RESPONSIBILITY SHALL CONTAIN ACKNOWLEDGMENT OF AWARENESS OF THE SPECIAL REQUIREMENTS CONTAINED IN THE STATEMENT OF SPECIAL INSPECTION.			SPECIAL INSPECTIONS REQUIRED (YES NO)								
				CONT PERIODIC N/A								
C	REQUIRED VERIFICATION AND INSPECTION OF SOILS (TO BE PERFORMED BY A LICENSED GEOTECHNICAL ENGINEER): 1. VERIFY MATERIALS BELOW SHALLOW FOUNDATIONS ARE ADEQUATE TO ACHIEVE THE DESIGN BEARING CAPACITY. 2. VERIFY EXCAVATIONS ARE EXTENDED TO PROPER DEPTH AND HAVE REACHED PROPER MATERIAL. 3. PERFORM CLASSIFICATION AND TESTING OF COMPACTED FILL MATERIALS. 4. PERFORM CLASSIFICATION AND TESTING OF NATIVE SOILS TO VERIFY ANY SOIL PROPERTIES ASSUMED AS PART OF DESIGN FOR THIS PROJECT IN THE ABSENCE OF A SOILS REPORT (SEE SOIL PROPERTIES ON THIS DRAWING). THIS TESTING SHALL BE PERFORMED IN ADVANCE OF ANY CONSTRUCTION. THE STRUCTURAL ENGINEER SHALL BE NOTIFIED IF THE ASSUMED VALUES ARE NOT VALID. 5. VERIFY USE OF PROPER MATERIALS, DENSITIES AND LIFT THICKNESSES DURING PLACEMENT AND COMPACTION OF COMPACTED FILL. 6. PRIOR TO PLACEMENT OF COMPACTED FILL, INSPECT SUBGRADE AND VERIFY THAT SITE HAS BEEN PREPARED PROPERLY.			1. INSPECTION TASKS AFTER WELDING A. WELDS CLEANED B. SIZE, LENGTH AND LOCATION OF WELDS C. WELDS MEET VISUAL ACCEPTANCE CRITERIA - CRACK PROHIBITION - WELD/BASE-METAL FUSION - CRATER CROSS SECTION - WELD PROFILES - WELD SIZE - UNDERCUT - POROSITY D. ARC STRIKES E. K-AREA - WHEN WELDING OF DOUBLER PLATES, CONTINUITY PLATES OR STIFFENERS HAS BEEN PERFORMED IN THE K-AREA, VISUALLY INSPECT THE WEB K-AREA FOR CRACKS WITHIN 3 IN. (75 MM) OF THE WELD F. WELD ACCESS HOLES IN ROLLED HEAVY SHAPES AND BUILT-UP HEAVY SHAPES - AFTER ROLLED HEAVY SHAPES (SEE AISC SECTION A3.1C) AND BUILT-UP SHAPES (SEE AISC SECTION A3.1D) ARE WELDED, VISUALLY INSPECT THE WELD ACCESS HOLE FOR CRACKS G. BACKING REMOVED AND WELD TABS REMOVED (IF REQUIRED). H. REPAIR ACTIVITIES I. DOCUMENT ACCEPTANCE OR REJECTION OF WELDED JOINT OR MEMBER J. NO PROHIBITED WELDS HAVE BEEN ADDED WITHOUT THE APPROVAL OF THE EOR.								
B	CONCRETE CONSTRUCTION: 1. INSPECT REINFORCMENT, INCLUDING PRESTRESSING TENDONS, AND PLACEMENT 2. REINFORCING BAR WELDING: A. VERIFY WELDABILITY OF REINFORCING BARS OTHER THAN ASTM A706 B. INSPECT SINGLE-PASS FILLET WELD, MAXIMUM 5/16", AND C. INSPECT ALL OTHER WELDS. 3. INSPECTION OF ANCHORS CAST IN CONCRETE 4. INSPECTION OF ANCHORS POST-INSTALLED IN HARDENED CONCRETE MEMBERS A. ADHESIVE ANCHORS INSTALLED IN HORIZONTALLY OR UPWARDLY INCLINED ORIENTATIONS TO RESIST SUSTAINED TENSION LOADS B. MECHANICAL ANCHORS AND ADHESIVE ANCHORS NOT DEFINED IN 4.A 5. VERIFYING USE OF REQUIRED DESIGN MIX 6. PRIOR TO CONCRETE PLACEMENT, FABRICATE SPECIMENS FOR STRENGTH TESTS, PERFORM SLUMP AND AIR CONTENT TESTS, AND DETERMINE THE TEMPERATURE OF THE CONCRETE. 7. INSPECT CONCRETE AND SHOTCRETE PLACEMENT FOR PROPER APPLICATION TECHNIQUES 8. VERIFY MAINTENANCE OF SPECIFIED CURING TEMPERATURE AND TECHNIQUES 9. INSPECT PRESTRESSED CONCRETE FOR: A. APPLICATION OF PRESTRESSING FORCES; AND B. GROUTING OF BONDED PRESTRESSING TENDONS. 10. INSPECT ERECTION OF PRECAST CONCRETE MEMBERS 11. VERIFY IN-SITU CONCRETE STRENGTH, PRIOR TO STRESSING OF TENDONS IN POST-TENSIONED CONCRETE AND PRIOR TO REMOVAL OF SHORES AND FORMS FROM BEAMS AND STRUCTURAL SLABS 12. INSPECT FORMWORK FOR SHAPE, LOCATION AND DIMENSIONS OF CONCRETE MEMBER BEING FORMED											
A												




TETRA TECH

www.tetrattech.com

160 East Via Verde, Suite 240  
San Dimas, California, 91773  
Phone: (909) 305-2930 Fax: (909) 305-2959



4/18/25



MARK	DATE	DESCRIPTION	BY

MONTECITO WATER DISTRICT

RESERVOIR SEISMIC RETROFIT AND REPLACEMENT PROJECT FOR PARK LANE RESERVOIR

SPECIAL INSPECTIONS AND STRUCTURAL OBSERVATIONS

Project No.: 200-106490-21001

Designed By: GH

Drawn By: EJH


Checked By: VMR

S-002

Bar Measures 1 inch



4/18/2025 2:29:25 PM - N:\T\LOCAL\PROJECTS\IRVINE\106490\21001\CAD\SHSHEETFILES\PARK LANE\S-101-DEMO.DWG - HUTCHINS, ERIC



FOUNDATION DEMOLITION PLAN


SCALE: 1/8"=1'-0"

KEYNOTES:

1. CONCRETE FLOOR SLAB, PROTECT IN PLACE. (POWER WASH AND REMOVE ALL SILL ON FLOOR SLAB).
2. REMOVE AND DISPOSE OF EXISTING 3 1/2" DIAMETER CONCRETE FILLED STEEL COLUMNS AND CONCRETE PEDESTALS, TYPICAL OF 48.
3. EXISTING CONCRETE WALL, PROTECT IN PLACE. PROVIDE TEMPORARY SHORNING, BRACING, UNDERPINNING, ETC. AS REQUIRED TO MAINTAIN THE ALIGNMENT, POSITION AND INTEGRITY OF THE EXISTING WALLS.
4. CUT OFF EXISTING LADDER RUNGS FLUSH WITH FACE OF EXISTING WALL, REMOVE AND DISPOSE. TYPICAL AT FOUR LOCATIONS.
5. REMOVE AND DISPOSE OF EXISTING 2x8 WOOD ROOF JOISTS @ 46" ON CENTER.
6. REMOVE AND DISPOSE OF EXISTING DOUBLE 2x10 WOOD GIRDERS.
7. REMOVE AND DISPOSE OF EXISTING CORRUGATED GALVANIZED STEEL ROOFING PANELS.

NOTE:

THE DIMENSIONS SHOWN ON THESE PLAN ARE BASED RECORD DRAWINGS AND SURVEY INFORMATION. THE CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS.



**TETRA TECH**

www.tetratech.com

160 East Via Verde, Suite 240  
San Dimas, California, 91773  
Phone: (909) 305-2930 Fax: (909) 305-2959



4/18/25



MARK	DATE	DESCRIPTION	BY


MONTECITO WATER DISTRICT  
RESERVOIR SEISMIC RETROFIT AND REPLACEMENT  
PROJECT FOR PARK LANE RESERVOIR

DEMOLITION PLAN

Project No.: 200-106490-21001  
Designed By: VMR  
Drawn By: EJJ  
Checked By: VMR

**S-101**

Bar Measures 1 inch




ROOF FRAMING DEMOLITION PLAN


SCALE: 3/16"=1'-0"



4/18/2025 2:29:47 PM - N:\LOCAL\PROJECTS\IRVINE\106490-2\1001\CAD\DWG\106490-2\1001\DEMOS\106490-2\1001\DEMOS.DWG - HUTCHINS, ERIC



**A** DEMOLITION ELEVATION AND LONGITUDINAL SECTION  
SCALE: 1/4"=1'-0"




**B** DEMOLITION TRANSVERSE SECTION  
SCALE: 3/8"=1'-0"

**KEYNOTES:**



1. CONCRETE FLOOR SLAB, PROTECT IN PLACE. (POWER WASH AND REMOVE ALL SILL ON THE FLOOR SLAB).
2. REMOVE AND DISPOSE OF EXISTING 3 1/2" DIAMETER CONCRETE FILLED STEEL COLUMNS AND CONCRETE PEDESTALS (CUT PEDESTAL FLUSH WITH TOP OF CONCRETE FLOOR SLAB), TYPICAL OF 48.
3. EXISTING CONCRETE WALL, PROTECT IN PLACE.
4. REMOVE AND DISPOSE OF EXISTING CONCRETE CURB.
5. REMOVE AND DISPOSE OF EXISTING 2x4 WOOD BRACES.
6. REMOVE AND DISPOSE OF EXISTING CORRUGATED GALVANIZED STEEL ROOFING PANELS.
7. REMOVE AND DISPOSE OF EXISTING GALVANIZED STEEL SCREEN ON ALL FOUR SIDES OF RESERVOIR.
8. REMOVE AND DISPOSE OF EXISTING 3'-0" LONG 6x6 WOOD CORBEL AT TOPS OF COLUMNS.
9. REMOVE AND DISPOSE OF EXISTING DOUBLE 2x10 WOOD GIRDERS.
10. REMOVE AND DISPOSE OF EXISTING 2x4 WOOD BRACES.
11. REMOVE AND DISPOSE OF EXISTING 2x8 WOOD ROOF JOISTS @ 46" ON CENTER.
12. SHAVE OFF AND LEVEL TOP OF EXISTING WALL FOOTING FOR NEW WALL FOOTING CONSTRUCTION.
13. REMOVE AND DISPOSE OF EXISTING SILL PLATE.
14. G.C. TO PERFORM GROUND PENETRATING RADAR (GPR) SCAN TO THE EXISTING FLOOR SLAB TO CONFIRM THERE ARE NO VOID SPACE UNDER THE EXISTING SLAB. IF VOID IS DETECTED, PROVIDE A HEAT MAP SHOWING THE LOCATION OF THE VOID AND REMEDIATE THE VOID AS OUTLINED BELOW. IF THE AREA OF THE VOID IS LESS THAN 25 SQFT, REMEDIATE BY POLYURETHANE FOAM INJECTION. POLYURETHANE FOAM USED FOR INJECTION SHALL HAVE A MINIMUM DENSITY OF 4 PCF PER ASTM D1622 AND A MINIMUM PEAK COMPRESSIVE STRENGTH OF 100 PSI PER ASTM D1621. IF THE AREA OF THE VOID IS LARGER THAN 25 SQFT, REMEDIATE BY SAW CUT AND REMOVE THE EXISTING SLAB, THEN OVER EXCAVATE 2 FT OF SOIL, AND BACK FILL WITH A 2 SACK SLURRY.



**TETRA TECH**

www.tetrattech.com

160 East Via Verde, Suite 240  
San Dimas, California, 91773  
Phone: (909) 305-2930 Fax: (909) 305-2959



MARK	DATE	DESCRIPTION	BY

MONTECITO WATER DISTRICT  
RESERVOIR SEISMIC RETROFIT AND REPLACEMENT  
PROJECT FOR PARK LANE RESERVOIR  
**DEMOLITION SECTIONS  
AND ELEVATION**


Project No.: 200-106490-21001  
Designed By: VMR  
Drawn By: EJJH  
Checked By: VMR

**S-102**

Bar Measures 1 inch



4/18/2025 2:30:17 PM - N:\LOCAL\PROJECTS\IRVINE\106490-2\1001\CAD\DWG\PROJECTS\106490-2\1001\FOUNDATION.DWG - HUTCHINS, ERIC



**TETRA TECH**  
www.tetrattech.com  
160 East Via Verde, Suite 240  
San Dimas, California, 91773  
Phone: (909) 305-2930 Fax: (909) 305-2959

REGISTERED PROFESSIONAL ENGINEER  
WAN RONG ERIC YUEN  
No. 81177  
STRUCTURAL  
STATE OF CALIFORNIA  
4/18/25

**MONTECITO WATER DISTRICT**

MARK	DATE	DESCRIPTION	BY

**MONTECITO WATER DISTRICT**  
RESERVOIR SEISMIC RETROFIT AND REPLACEMENT  
PROJECT FOR PARK LANE RESERVOIR  
**FOUNDATION PLAN**


Project No.: 200-106490-21001  
Designed By: VMR  
Drawn By: E.J.H.  
Checked By: VMR  
**S-103**



4/18/2025 2:30:43 PM - N:\T\LOCAL\PROJECTS\IRVINE\106490-2\1001\CAD\SHEETFILES\PARK LANE\S-104-ROOFLAN.DWG - HUTCHINS, ERIC

# KEYNOTES:

- 9" THICK CONCRETE ROOF SLAB WITH #6 @ 8" EACH WAY TOP AND BOTTOM.
- OUTSIDE FACE OF NEW CONCRETE WALL BELOW (TYPICAL).
- EDGE OF ROOF DECK.
- 7'-4" SQUARE x 5 1/2" THICK CONCRETE DROP PANEL.
- 18" DIAMETER CONCRETE COLUMN BELOW.
- 4'x4' ALUMINUM FLUSH MOUNTED ACCESS HATCH, BILCO TYPE J-AL OR APPROVED EQUAL.
- 2'-0" SQUARE OPENING FOR VENT (TYPICAL 3 LOCATIONS).
- 6'-0"x8'-0" ALUMINUM FLUSH MOUNTED EQUIPMENT ACCESS HATCH, BILCO TYPE JD-AL OR APPROVED EQUAL. (TYPICAL 2 LOCATIONS).
- PROVIDE 4-#6 (x10'-0") ADDITIONAL TOP BARS EACH WAY AT EACH COLUMN. TYPICAL AT 24 LOCATIONS.
- SLOPE ROOF DECK AT APPROXIMATELY 2%.
- PREFABRICATED ALUMINUM LADDER.
- ALUMINUM GUARDRAIL.
- S.S. INTERIOR ACCESS LADDER.
- PIPE PENETRATION - SEE PIPING DRAWINGS FOR SIZE AND LOCATIONS.
- 2'x2' ALUMINUM FLUSH MOUNTED HATCH, BILCO TYPE J-AL OR APPROVED EQUAL IN ROOF SLAB FOR MUD VALVE OPERATOR, SEE DETAIL 10 ON SHEET S-502. CENTER AT THE DRAIN BELOW. (FIELD VERIFY LOCATION).
- CONSTRUCTION JOINT IN ROOF DECK, SEE DETAIL 9 ON SHEET S-501.
- CORNER REINFORCING PER DETAIL 8 ON SHEET S-502. TYPICAL AT ALL FOUR CORNERS.
- OVERFLOW WEIR BOX.
- OVERFLOW PIPE, SEE C-102.
- 3'-0" SQUARE ACCESS HATCH.
- STAFF GAUGE: MINIMUM 10" WIDE HDPE OR FRP BOARD WITH LINE MARKINGS AT 6" AND NUMBERS AT EACH WHOLE FOOT. LINES SHALL BE 1/2" WIDE; NUMBERS SHALL BE 3" HIGH. LINES AND NUMBERS SHALL BE BLACK ON A WHITE BACKGROUND. GAUGE SHALL BE ATTACHED TO THE WALL WITH TWO 1/4" DIAMETER EXPANSION ANCHORS @ 36" ON CENTER MAXIMUM. CONTRACTOR SHALL SUBMIT COMPLETE SHOP DRAWINGS FOR THE STAFF GAUGE AND FASTENERS PRIOR TO FABRICATION.
- ROOF SLAB PENETRATION FOR LEVEL INDICATOR, SEE DETAIL 2 ON SHEET S-503.



## ROOF DECK PLAN

SCALE: 1/8"=1'-0"

DATUM  
DATUM (0'-0") OCCURS AT THE TOP  
OF THE FLOOR SLAB AT THE EDGES  
OF THE WALL FOOTING AND IS AT  
ELEVATION 537.15.

- ### NOTES:
- CONCRETE SLAB SECTIONS SHALL BE DEFINED AS DIVIDED BY THE CONSTRUCTION JOINTS AS SHOWN ON THIS DRAWING.
  - CONCRETE SLAB SECTIONS SHALL NOT BE CAST AGAINST OTHER CONCRETE SLAB SECTIONS UNTIL A MINIMUM OF 3 FULL DAYS (72 HOURS) HAS ELAPSED SINCE THE PREVIOUS SECTION WAS PLACED AND FINISHED.
  - ALL LEVEL TRANSDUCER, ROOF HATCH INTRUSION ALARMS, ELECTRICAL CONDUITS, SCADA HOOKUP/REPROGRAMMING, ETC. WILL BE FURNISHED AND INSTALL BY THE DISTRICT.



**TETRA TECH**

www.tetrattech.com  
160 East Via Verde, Suite 240  
San Dimas, California, 91773  
Phone: (909) 305-2930 Fax: (909) 305-2959



4/18/25



MARK	DATE	DESCRIPTION	BY

MONTECITO WATER DISTRICT  
RESERVOIR SEISMIC RETROFIT AND REPLACEMENT  
PROJECT FOR PARK LANE RESERVOIR




ROOF DECK PLAN

Project No.: 200-106490-21001  
Designed By: VMR  
Drawn By: EJM  
Checked By: VMR

**S-104**


Bar Measures 1 inch






 <b>TETRA TECH</b>  www.tetrattech.com  160 East Via Verde, Suite 240 San Dimas, California, 91773 Phone: (909) 305-2930 Fax: (909) 305-2959			<table border="1"> <thead> <tr> <th>MARK</th> <th>DATE</th> <th>DESCRIPTION</th> <th>BY</th> </tr> </thead> <tbody> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td></tr> </tbody> </table>	MARK	DATE	DESCRIPTION	BY																																									<b>MONTECITO WATER DISTRICT</b>  RESERVOIR SEISMIC RETROFIT AND REPLACEMENT PROJECT FOR PARK LANE RESERVOIR	Project No.: 200-106490-21001 Designed By: VMR Drawn By: EJJ Checked By: VMR
				MARK	DATE	DESCRIPTION	BY																																										
SECTION	<b>S-301</b>																																																



4/18/2025 2:31:28 PM - N:\LOCAL\PROJECTS\IRVINE\106490\200-106490-21001\CAD\SHEETFILES\PARK LANE\S-302-SECTION.DWG - HUTCHINS, ERIC




**B** TYPICAL COLUMN DETAIL  
SCALE: 3/4"=1'-0"

 <b>TETRA TECH</b> www.tetrattech.com 160 East Via Verde, Suite 240 San Dimas, California, 91773 Phone: (909) 305-2930 Fax: (909) 305-2959			MARK	DATE	DESCRIPTION	BY	MONTECITO WATER DISTRICT RESERVOIR SEISMIC RETROFIT AND REPLACEMENT PROJECT FOR PARK LANE RESERVOIR	Project No.: 200-106490-21001
							Drawn By: EJM	<b>S-302</b>
							Checked By: VMR	


Bar Measures 1 inch




4/18/2025 2:31:46 PM - N:\LOCAL\PROJECTS\IRVINE\106490-21001\CAD\DWG\FILES\PARK LANE\303-SECTION.DWG - HUTCHINS, ERIC



**C** TYPICAL MIDDLE STRIP SECTION  
SCALE: 3/8"=1'-0"



**D** TYPICAL COLUMN STRIP SECTION  
SCALE: 3/8"=1'-0"



**TETRA TECH**

www.tetrattech.com

160 East Via Verde, Suite 240  
San Dimas, California, 91773  
Phone: (909) 305-2930 Fax: (909) 305-2959



4/18/25



MARK	DATE	DESCRIPTION	BY

MONTECITO WATER DISTRICT  
RESERVOIR SEISMIC RETROFIT AND REPLACEMENT  
PROJECT FOR PARK LANE RESERVOIR


ROOF SLAB CROSS SECTION

Project No.: 200-106490-21001  
Designed By: GH  
Drawn By: EJM  
Checked By: VMR

**S-303**

Bar Measures 1 inch






1 TYPICAL BAR BENDS  
SCALE: N.T.S.

REINFORCING LAP SPLICE SCHEDULE					
BAR	f <sub>c</sub> =2500	f <sub>c</sub> =3250	f <sub>c</sub> =4000	f <sub>c</sub> =4500	f <sub>c</sub> =5000
	L (inches)	L (inches)	L (inches)	L (inches)	L (inches)
3	24	21	19	18	17
4	32	28	25	24	23
5	39	35	31	30	28
6	47	42	37	35	34
7	69	60	54	51	49
8	78	69	62	59	56


- NOTES:
- LAPS SHOWN IN THIS TABLE ARE CLASS B, CATEGORY 3 TYPE SPLICES. LAP LENGTH IS BASED UPON SMALLER OF TWO BARS BEING SPLICED WHEN NOT THE SAME SIZE.
  - INCREASE LAP LENGTHS BY A FACTOR OF 1.3 FOR HORIZONTAL REINFORCEMENT SO PLACED THAT MORE THAN 12 INCHES OF CONCRETE IS CAST IN THE MEMBER BELOW THIS REINFORCEMENT.

2 REINFORCING LAP SPLICE SCHEDULE  
SCALE: N.T.S.




- NOTE:
- ALL SPLICES SHALL BE MADE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS. SUBMIT SHOP DRAWINGS PRIOR TO FABRICATION INSTALLATION OR SPLICING WATERSTOPS.
- ALL SPLICES IN WATERSTOPS AT INTERSECTIONS AND CHANGES IN DIRECTION SHALL BE SHOP MITERED AND WELDED. ONLY BUTT SPLICES MAY BE PERFORMED IN THE FIELD. ALL SPLICES SHALL BE SUBJECT TO INSPECTION AND APPROVAL BY THE ENGINEER, MANUFACTURER AND/OR DISTRICT.


3 WATERSTOP SCHEDULE  
SCALE: N.T.S.




4 ADDITIONAL REINFORCING AT PENETRATIONS  
SCALE: N.T.S.




5 TYPICAL ROOF SLAB OPENINGS  
SCALE: N.T.S.




6 TYPICAL FOUNDATION CONSTRUCTION JOINT  
SCALE: 1/2"=1'-0"



7 WALL CORNER DETAIL  
SCALE: 1/2"=1'-0"



8 TYPICAL VERTICAL WALL JOINT  
SCALE: 3/4" = 1'-0"



9 TYPICAL ROOF SLAB CONSTRUCTION JOINT  
SCALE: 1"=1'-0"

10 NOT USED  
SCALE:

11 NOT USED  
SCALE:

12 NOT USED  
SCALE:



MARK	DATE	DESCRIPTION	BY

MONTECITO WATER DISTRICT  
RESERVOIR SEISMIC RETROFIT AND REPLACEMENT  
PROJECT FOR PARK LANE RESERVOIR

STRUCTURAL DETAILS 1

Project No.: 200-106490-21001  
Designed By: GH  
Drawn By: EJJ  
Checked By: VMR


S-501

Bar Measures 1 inch




4/18/2025 2:32:24 PM - N:\T\LOCAL\PROJECTS\IRVINE\106490-2\1001\CAD\DETAILS\FILES\DETAILS DWG - HUTCHINS, ERIC


1 NOT USED  
SCALE: N.T.S.




5 ROOF VENT OPENING  
SCALE: 1"=1'-0"




8 TYPICAL ROOF SLAB CORNER REINFORCING  
SCALE: 1"=1'-0"




2 OVERLOW WEIR (PLAN VIEW)  
SCALE: 1/2"=1'-0"




9 HATCH RISER DETAIL  
SCALE: 1"=1'-0"




3 OVEFLOW WEIR SECTION  
SCALE: 1/2"=1'-0"




6 TYPICAL LADDER DETAIL (PLAN)  
SCALE: 3/4"=1'-0"




10 MUD VALVE OPERATOR ACCESS HATCH  
SCALE: 1 1/2"=1'-0"



4 TYPICAL LADDER DETAIL (SECTION)  
SCALE: 3/4"=1'-0"



7 LADDER DETAIL (ELEVATION)  
SCALE: 3/4"=1'-0"



11 LADDER BASE CONNECTION  
SCALE: 3/4"=1'-0"

**TETRA TECH**  
www.tetrattech.com  
160 East Via Verde, Suite 240  
San Dimas, California, 91773  
Phone: (909) 305-2930 Fax: (909) 305-2959

REGISTERED PROFESSIONAL ENGINEER  
ERIC HUTCHINS  
No. 81177  
STRUCTURAL  
STATE OF CALIFORNIA  
4/18/25

**MONTECITO WATER DISTRICT**

MARK	DATE	DESCRIPTION	BY

MONTECITO WATER DISTRICT  
RESERVOIR SEISMIC RETROFIT AND REPLACEMENT  
PROJECT FOR PARK LANE RESERVOIR

STRUCTURAL DETAILS 2


Project No.: 200-106490-21001  
Designed By: GH  
Drawn By: EJJH  
Checked By: VMR

S-502

Bar Measures 1 inch



4/18/2025 2:32:42 PM - N:\T\LOCAL\PROJECTS\IRVINE\106490\200-106490-2\1001\CAD\SHEETFILES\PARK LANE\S-503-DETAILS.DWG - HUTCHINS, ERIC



4 NOT USED  
SCALE:

5 NOT USED  
SCALE:

6 NOT USED  
SCALE:

3 NOT USED  
SCALE:

Tt

TETRA TECH

www.tetratech.com

160 East Via Verde, Suite 240  
San Dimas, California, 91773  
Phone: (909) 305-2930 Fax: (909) 305-2959

REGISTERED PROFESSIONAL ENGINEER  
WANG JONG ERIC YUEN  
No. 8177  
STRUCTURAL  
STATE OF CALIFORNIA  
4/18/25

MONTECITO  
WATER DISTRICT

MARK	DATE	DESCRIPTION	BY

MONTECITO WATER DISTRICT

RESERVOIR SEISMIC RETROFIT AND REPLACEMENT  
PROJECT FOR PARK LANE RESERVOIR

STRUCTURAL DETAILS 3

Project No.: 200-106490-21001

Designed By: GH

Drawn By: EJH

Checked By: VMR

S-503

Bar Measures 1 inch



