



MONTECITO WATER DISTRICT

160 East Via Verde, Suite 240
San Dimas, California, 91773
PHONE: (909) 305-2930 FAX: (909) 305-2959



www.tetrattech.com

RESERVOIR SEISMIC RETROFIT AND
REPLACEMENT PROJECT FOR TERMINAL RESERVOIR



PROJECT LOCATION: E. MOUNTAIN DR.,
MONTECITO, CALIFORNIA
34.45528, -119.66058

CLIENT INFORMATION: MONTECITO WATER DISTRICT
583 San Ysidro Rd
Montercito, CA 93108

Tt PROJECT No.: 200-106490-21001

CLIENT PROJECT No.: P133

PROJECT DESCRIPTION / NOTES:
REPLACEMENT OF THE DETERIORATED STEEL ROOF FRAMING, STEEL ROOFING
PANELS AND STEEL COLUMNS WITH NEW CONCRETE ROOF DECK, CONCRETE SLAB
OVERLAY AND CONCRETE COLUMNS. STRENGTHENING OF THE EXTERIOR WALLS
AND WALL FOOTINGS. IMPROVEMENTS TO INLET/OUTLET AND OVERFLOW PIPING.



ISSUED:
06/15/2021: 60 PERCENT DESIGN REVIEW
09/16/2021: 90 PERCENT DESIGN REVIEW
12/16/2021: DRAFT FINAL SUBMITTAL
05/16/2025: FINAL SUBMITTAL

SHEET INDEX

SHEET NO.	DESCRIPTION
COVER	COVER SHEET
C-101	INTERIOR INLET/OUTLET PIPING
C-102	INLET OUTLET PIPING CONT.
C-501	CIVIL DETAILS
S-001	GENERAL STRUCTURAL NOTES
S-002	SPECIAL INSPECTIONS AND STRUCTURAL OBSERVATIONS
S-101	DEMOLITION PLAN
S-102	FOUNDATION PLAN
S-103	ROOF DECK PLAN
S-301	WALL RETROFIT SECTIONS
S-302	ROOF SLAB CROSS SECTION
S-501	STRUCTURAL DETAILS 1
S-502	STRUCTURAL DETAILS 2
S-503	STRUCTURAL DETAILS 3
S-504	STRUCTURAL DETAILS 4
S-505	STRUCTURAL DETAILS 5


LOCATION MAP:

VICINITY MAP:



5/16/25

5/15/2025 5:57:58 PM - O:\PROJECTS\IRVINE\106490\200-106490-21001\CAD\SHEETFILES\TERMINAL\C-101-INLET/OUTLET PIPING.DWG - HEINEN, GEOFF





TETRA TECH
www.tetrattech.com
160 East Via Verde, Suite 200
San Dimas, California, 91773
Phone: (909) 305-2930 Fax: (909) 305-2959



05/09/25



MARK	DATE	DESCRIPTION	BY

MONTECITO WATER DISTRICT



RESERVOIR SEISMIC RETROFIT AND REPLACEMENT
PROJECT FOR TERMINAL RESERVOIR

INTERIOR INLET/OUTLET PIPING


Project No.: 200-106490-21001
Designed By: AML
Drawn By: AS
Checked By: KRB

C-101

5/15/2025 6:00:28 PM - O:\PROJECTS\IRVINE\106490\200-106490-21001\CAD\SHEETFILES\TERMINAL\C-102-INLET/OUTLET/PIPING\CONT.DWG - HEINEN, GEOFF



1 CIPP EXCAVATION DETAIL
SCALE: N.T.S.



TETRA TECH

www.tetrattech.com

160 East Via Verde, Suite 200
San Dimas, California, 91773
Phone: (909) 305-2930 Fax: (909) 305-2959




MARK	DATE	DESCRIPTION	BY

MONTECITO WATER DISTRICT
RESERVOIR SEISMIC RETROFIT AND REPLACEMENT
PROJECT FOR TERMINAL RESERVOIR
INLET/OUTLET PIPING (CONT.)




Project No.: 200-106490-21001
Designed By: AML
Drawn By: AS
Checked By: KRB


C-102

Bar Measures 1 inch



- NOTES:
- SS VALVE EXTENSION SIZE SHALL BE DETERMINED BY VALVE MANUFACTURER
 - PROVIDE MINIMUM OF TWO (2) UNIVERSAL JOINTS ON VALVE STEM TO AID IN ALIGNING STEM AND VALVE NUT. ALL MATERIAL SHALL BE STAINLESS STEEL. LOCATION OF UNWELDED JOINTS PER MANUFACTURER'S RECOMMENDATION.
 - CONTRACTOR SHALL EXERCISE EXTREME CARE WHILE INSTALLING VALVE OPERATOR ACCESS HATCH. CONTRACTOR SHALL USE LASER LEVEL TO MAINTAIN VALVE STEM PLUMBNESS.



**TETRA TECH**
www.tetrattech.com
160 East Via Verde, Suite 200
San Dimas, California, 91773
Phone: (909) 305-2930 Fax: (909) 305-2959





MARK	DATE	DESCRIPTION	BY

MONTECITO WATER DISTRICT
RESERVOIR SEISMIC RETROFIT AND REPLACEMENT
PROJECT FOR TERMINAL RESERVOIR
CIVIL DETAILS

Project No.: 200-106490-21001
Designed By: AML
Drawn By: AS
Checked By: KRB

C-501

5/15/2025 6:02:08 PM - O:\PROJECTS\IRVINE\106490-21001\CAD\SHEETFILES\TERMINAL\C-501-CIVILDETAILS.DWG - HEINEN, GEOFF

5/15/2025 6:03:15 PM - C:\PROJECTS\IRVINE\106490\200-106490-21001\CAD\SHEETFILES\TERMINALS-001-GENNOTES.DWG - HEINEN, GEOFF

GENERAL STRUCTURAL NOTES
THESE NOTES SHALL APPLY UNLESS SHOWN/INDICATED OTHERWISE ELSEWHERE IN THE STRUCTURAL DRAWINGS.

GENERAL

- ALL MATERIALS AND CONSTRUCTION SHALL CONFORM TO THE 2019 CALIFORNIA BUILDING CODE (C.B.C.) BASED UPON THE 2018 EDITION OF THE INTERNATIONAL BUILDING CODE (I.B.C.).
- CONTRACTOR SHALL VERIFY ALL EXISTING CONDITIONS AND DIMENSIONS BEFORE STARTING WORK. DIMENSIONS OF (E) CONSTRUCTION WHERE SHOWN ON THESE DRAWINGS ARE NOMINAL AND SHOULD BE FIELD VERIFIED. SHOULD CONDITIONS EXIST WHICH ARE CONTRARY TO THOSE SHOWN ON PLANS, THE ENGINEER SHALL BE NOTIFIED IN WRITING BEFORE PROCEEDING WITH WORK.
- CONTRACTOR SHALL VERIFY ALL EXISTING CONDITIONS AND DIMENSIONS BEFORE STARTING WORK. SHOULD CONDITIONS EXIST WHICH ARE CONTRARY TO THOSE SHOWN ON PLANS, THE ENGINEER SHALL BE NOTIFIED IN WRITING BEFORE PROCEEDING WITH WORK.
- IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO ENSURE THAT ALL COLUMNS, FRAMING, BEAMS, ETC. ARE ADEQUATELY BRACED AND SHORED DURING CONSTRUCTION. ALL BRACING/SHORING SHALL BE DESIGNED BY A REGISTERED ENGINEER HIRED BY THE CONTRACTOR. BRACING OF CONCRETE WALLS AND COLUMNS SHALL REMAIN IN PLACE UNTIL RETROFIT WORK IS COMPLETE.
- UNLESS DETAILED, SPECIFIED, OR INDICATED OTHERWISE, CONSTRUCTION SHALL BE AS INDICATED IN THE APPLICABLE TYPICAL DETAILS AND THESE GENERAL NOTES. TYPICAL DETAILS ARE MEANT TO APPLY EVEN THOUGH NOT REFERENCED AT SPECIFIC LOCATIONS ON DRAWINGS WHERE THE OCCUR.
- THE CONTRACT DRAWINGS AND SPECIFICATIONS REPRESENT THE FINISHED STRUCTURE. THEY DO NOT INDICATE THE METHOD OF CONSTRUCTION. THE CONTRACTOR SHALL PROVIDE ALL MEASURES NECESSARY TO PROTECT THE STRUCTURE, WORKERS AND PEDESTRIANS DURING CONSTRUCTION. SUCH MEASURES SHALL INCLUDE, BUT NOT BE LIMITED TO BRACING, SHORING FOR LOADS DUE TO CONSTRUCTION EQUIPMENT, TEMPORARY STRUCTURES, AND PARTIALLY COMPLETED WORK, ETC. OBSERVATION VISITS TO THE SITE BY THE ENGINEER SHALL NOT BE CONSIDERED AS INSPECTION OF SUCH ITEMS.
- DIMENSIONS SHALL TAKE PRECEDENCE OVER SCALES SHOWN ON DRAWINGS.
- ALL ITEMS REMOVED DURING CONSTRUCTION WORK SHALL BE REPLACED TO MATCH EXISTING.
- ALL WORK SHALL CONFORM TO THE PLANS AND SPECIFICATIONS IN ALL RESPECTS AND SHALL BE SUBJECT TO APPROVAL BY THE ENGINEER.
- ASSUMED SOIL BEARING CAPACITY OF 2000 PSF IS BASED ON THE PRESCRIPTIVE VALUES FROM TABLE 1806.2 OF THE 2019 CBC FOR MATERIAL CLASS 4.0.
- CONTRACTOR SHALL VERIFY LOCATION OF ALL SITE UTILITIES PRIOR TO STARTING WORK, BOTH ABOVE GROUND AND BELOW GROUND, WHICH MAY BE IMPACTED BY THE WORK SHOWN ON THESE DRAWINGS. ANY CONFLICTS SHALL BE BROUGHT TO THE ATTENTION OF THE ENGINEER.
- CONTRACTOR SHALL DEFEND, INDEMNIFY AND HOLD THE CLIENT AND TETRA TECH, INC. THEIR PARENT AND SUBSIDIARY COMPANIES, ITS EMPLOYEES, OFFICERS, OR AGENTS, HARMLESS AGAINST ANY AND ALL CLAIMS BY ANY PARTIES ARISING FROM, OR RELATED TO, ANY AND ALL DAMAGES, INCLUDING LEGAL COSTS AND ATTORNEY'S FEES, RESULTING FROM INTERFERENCE WITH, INTERRUPTION OF, DAMAGE TO, OR ANY AND ALL INJURIES WHICH RESULT FROM DAMAGE CAUSED TO SUBSURFACE INSTALLATION, WHICH IS UNFORESEEN AND DESPITE ENGINEER'S EFFORT DURING THE DESIGN PROCESS WAS NOT LOCATED, EXCEPTING ONLY THE GROSS NEGLIGENCE OR WILLFUL MISCONDUCT OF ENGINEER IN PROVIDING ITS SERVICES.
- ALL ITEMS SHOWN ON THESE PLANS ARE NEW UNLESS NOTED (E), EXIST. OR EXISTING.

REINFORCING NOTES

- REINFORCEMENT FOR CONCRETE SHALL BE DEFORMED BARS CONFORMING TO A.S.T.M. SPECIFICATION A615 (A706/A706M FOR WELDED REINFORCING). GRADE 60 STEEL SHALL BE USED
- ALL REINFORCEMENT, ANCHOR BOLTS, AND OTHER ANCHORAGES PLACED IN CONCRETE SHALL BE ACCURATELY PLACED AND POSITIVELY SECURED AND SUPPORTED BY CONCRETE BLOCKS, METAL CHAIRS, SPACERS, OR METAL HANGERS, AND SHALL BE IN POSITION BEFORE CONCRETE PLACING OR GROUTING IS BEGUN. DETAILING AND PLACING OF BARS SHALL CONFORM TO THE A.C.I. MANUAL OF STANDARD PRACTICES.
- BARS SPECIFIED AS "CONTINUOUS" SHALL EXTEND THE FULL LENGTH OF THE MEMBER CONTAINING THEM AND MAY BE SPLICED (UNLESS NOTED OR SHOWN WITHOUT SPLICES ON THE PLANS). IN CONCRETE, PROVIDE LAPS PER DETAIL 2 ON SHEET S-501. STAGGER ALL SPLICES.
- DOWELS SHALL BE PROVIDED AT ALL POUR JOINTS AND SHALL BE THE SAME SIZE AND SPACING AS REINFORCING DIRECTLY BEYOND POUR JOINTS.
- WELDING OF REINFORCING STEEL, METAL INSERTS AND CONNECTIONS IN REINFORCED CONCRETE CONSTRUCTION SHALL CONFORM TO ANSI/AWS D1.4-11. USE LOW HYDROGEN E-70 SERIES ELECTRODES FOR WELDING OF REINFORCING BARS. CONTINUOUS INSPECTION IS REQUIRED OF ALL FIELD WELDING IN ACCORDANCE WITH C.B.C. CHAPTER 17.

CONCRETE NOTES

- ALL CONCRETE FOR STRUCTURES SHALL HAVE A MINIMUM ULTIMATE COMPRESSIVE STRENGTH OF 4500 PSI AT 28 DAYS. AGGREGATES SHALL CONFORM TO A.S.T.M. C33. REFER TO THE SPECIFICATIONS FOR THE STRENGTH OF CONCRETE FOR OTHER APPLICATIONS
- CEMENT FOR CONCRETE SHALL BE TYPE V PORTLAND CEMENT CONFORMING TO A.S.T.M. C150.
- CONCRETE COVER FOR REINFORCING BARS SHALL BE:
CAST AGAINST AND PERMANENTLY EXPOSED TO EARTH = 3"
EXPOSED TO EARTH OR WEATHER: NO. 6 THROUGH NO. 18 BARS = 2"
NO. 5 BARS, W31 OR D31 WIRE, AND SMALLER = 1 1/2"
NOT EXPOSED TO WEATHER OR IN CONTACT WITH THE GROUND:
SLABS, WALLS, JOISTS: NO. 14 AND NO. 18 BARS = 1 1/2"
NO. 11 BARS AND SMALLER = 3/4"
BEAMS, COLUMNS: PRIMARY REINFORCEMENT, TIES, STIRRUPS, SPIRALS = 1 1/2"
- DRYPACK SHALL BE 1 PART CEMENT AND 3 PARTS SAND (BY VOLUME).
- NO PIPES OR DUCTS SHALL BE PLACED IN STRUCTURAL CONCRETE UNLESS SPECIFICALLY DETAILED. SEE MECHANICAL AND/OR ELECTRICAL DRAWINGS FOR LOCATION OF SLEEVES THROUGH WALLS AND FLOORS.
- THE LOCATION OF ALL CONSTRUCTION JOINTS NOT SPECIFICALLY NOTED OR SHOWN SHALL BE APPROVED BY THE STRUCTURAL ENGINEER.
- "ROUGHENED SURFACES", WHERE SPECIFIED ON THE DRAWINGS, SHALL BE MECHANICALLY ROUGHENED SUCH THAT A 1/4" AMPLITUDE (±) IS ACHIEVED BETWEEN HIGH AND LOW SPOTS OF THE ROUGHENED SURFACE. THE SURFACE SHALL BE CLEAN AND FREE OF LAITANCE

STEEL NOTES

- ALL WIDE FLANGE MEMBERS SHALL BE IN ACCORDANCE WITH A.S.T.M. A-992. ALL OTHER STRUCTURAL AND MISCELLANEOUS STEEL SHALL BE ASTM A36 UNLESS NOTED OTHERWISE. STRUCTURAL STEEL SHALL BE FABRICATED AND ERECTED IN ACCORDANCE WITH THE AISC SPECIFICATION FOR THE DESIGN, FABRICATION AND ERECTION OF STRUCTURAL STEEL FOR BUILDINGS. SPECIAL INSPECTION SHALL BE PROVIDED FOR ALL STRUCTURAL STEEL IN ACCORDANCE WITH CBC SECTION 1705.2.1. UNLESS FABRICATION IS PERFORMED ON THE PREMISES OF A FABRICATOR REGISTERED AND APPROVED TO PERFORM SUCH WORK WITHOUT SPECIAL INSPECTION, IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS AND SECTION 1704.2.5.2 OF THE 2019 CBC. AT THE COMPLETION OF FABRICATION, THE APPROVED FABRICATOR SHALL SUBMIT A CERTIFICATE OF COMPLIANCE TO THE CITY BUILDING OFFICIAL (OR OWNER IF THE PROJECT IS NOT UNDER THE JURISDICTION OF A BUILDING DEPARTMENT) AND TO THE ENGINEER STATING THAT THE WORK WAS PERFORMED IN ACCORDANCE WITH THE CONTRACT DOCUMENTS.
- STEEL TUBES SHALL CONFORM TO A.S.T.M. A500, GRADE B OR BETTER, UNLESS NOTED OTHERWISE.
- STEEL PIPES SHALL CONFORM TO A.S.T.M. A53, GRADE B.
- BOLTS SHALL CONFORM TO A.S.T.M. A307 OR BETTER, UNLESS NOTED OTHERWISE.
- HOLES FOR BOLTS IN STEEL SHALL BE OF SAME DIAMETER AS BOLT +1/16" MAXIMUM.
- ALL WELDING SHALL BE SHIELDED ARC TYPE AND SHALL BE PERFORMED BY A CERTIFIED WELDER IN A FABRICATION SHOP REGISTERED AND APPROVED IN ACCORDANCE WITH NOTE 1 ABOVE. CONTINUOUS INSPECTION IS REQUIRED OF ALL FIELD WELDING IN ACCORDANCE WITH AWS D1.1.
- NO STRUCTURAL STEEL MEMBER SHALL BE CUT FOR PIPES, DUCTS, ETC. UNLESS SPECIFICALLY DETAILED AND APPROVED BY STRUCTURAL ENGINEER.
- STAINLESS STEEL SHALL CONFORM TO A.S.T.M. A276/A.I.S.I. 316. STAINLESS STEEL BOLTS SHALL CONFORM TO A.S.T.M. F593. STAINLESS STEEL NUTS SHALL CONFORM TO A.S.T.M. F594.
- WELDING OF STAINLESS STEEL SHALL CONFORM TO STRUCTURAL WELDING CODE - STAINLESS STEEL, ANSI/AWS D1.6-07.
- WHERE SPECIFIED, USE OF HIGH-STRENGTH BOLTS SHALL CONFORM TO THE PROVISIONS OF THE "SPECIFICATION FOR STRUCTURAL JOINTS USING A.S.T.M. A325 OR A490 BOLTS" APPROVED BY THE RESEARCH COUNCIL ON STRUCTURAL CONNECTIONS OF THE ENGINEERING FOUNDATION (RCSC). SPECIAL INSPECTION OF HIGH-STRENGTH BOLT CONNECTIONS IS REQUIRED.
- ALL NON-STAINLESS STEEL EXPOSED TO WEATHER SHALL BE HOT-DIP GALVANIZED IN ACCORDANCE WITH ASTM A123 OR A153, AS APPLICABLE. REPAIR OF DAMAGED GALVANIZED COATING SHALL BE IN ACCORDANCE WITH ASTM A780. ALL OTHER NON-STAINLESS STEEL SHALL BE COATED WITH TWO COATS OF SHOP APPLIED PRIMER.
- WELDING EQUIPMENT SHALL BE CHECKED PRIOR TO WELDING AS REQUIRED BY AISC 360-16 TABLE N5.4-1.
- PRE-INSTALLATION VERIFICATION TESTING BY INSTALLATION PERSONNEL OBSERVED AND DOCUMENTED FOR FASTENER ASSEMBLIES AND METHODS USED SHALL BE PERFORMED AS REQUIRED BY AISC 360-16 TABLE N5.6-1

ADHESIVE ANCHORS

- ADHESIVE ANCHORS SHALL BE "SET-3G" ADHESIVE ANCHORS, MANUFACTURED BY SIMPSON STRONG-TIE.
- ANCHORS SHALL BE INSTALLED IN ACCORDANCE WITH I.C.C. EVALUATION REPORT ESR-4057.
- SPECIAL INSPECTION PER CHAPTER 1704.13 OF THE C.B.C. SHALL BE PROVIDED DURING ANCHOR INSTALLATION.
- AN ALTERNATIVE ADHESIVE ANCHOR PRODUCT MAY BE SUBMITTED TO THE ENGINEER FOR APPROVAL, PROVIDED THAT IT HAS A CURRENT I.C.C. EVALUATION REPORT APPROVAL.
- ALL ABANDONED HOLES SHALL BE FILLED WITH A DRYPACK GROUT. A MINIMUM 28-DAY COMPRESSIVE STRENGTH OF 5,000 PSI. THE FILLED HOLE(S) SHALL BE PREPARED AND CLEANED AS REQUIRED BY THE GROUT MANUFACTURER.
- LOCATE EXISTING REINFORCING USING A NON-DESTRUCTIVE METHOD (PACHOMETER OR OTHER), PRIOR TO DRILLING HOLES FOR ANCHORS. MAINTAIN A MINIMUM CLEARANCE OF 1" BETWEEN THE REINFORCEMENT AND THE ANCHOR.

DESIGN CRITERIA

DESIGN CODES AND REFERENCES:

- CALIFORNIA BUILDING CODE, 2019 EDITION
- ASCE/SEI 7-16 MINIMUM DESIGN LOADS FOR BUILDINGS & OTHER STRUCTURES
- ACI 318-14 BUILDING CODE REQUIREMENTS FOR STRUCTURAL CONCRETE
- ACI 350 CODE REQUIREMENTS FOR ENVIRONMENTAL ENGINEERING CONCRETE STRUCTURES
- ACI 350.3-06 SEISMIC DESIGN OF LIQUID CONTAINING CONCRETE STRUCTURES

ROOF LOADING:

- DEAD LOAD = 5 PSF (SOLAR PANEL ALLOWANCE)
- SELF WEIGHT OF CONCRETE DEAD LOAD = 110 PSF (8 INCH CONCRETE SLAB)
- LIVE LOAD = 100 PSF (ROOF SLAB DESIGN ONLY)
- LIVE LOAD = 40 PSF (COLUMN AND WALL DESIGN ONLY)

SEISMIC DESIGN PARAMETERS:

- ANALYSIS PROCEDURE USED: EQUIVALENT LATERAL FORCE PROCEDURE
- LOCATION: LAT. 34.45528 N, LONG. 119.66058 W
- OCCUPANCY CATEGORY: IV
- SITE CLASS: D
- SEISMIC DESIGN CATEGORY: F
- S1 = 0.759 Fa = 1.200 Ss = 2.056
- SD1 = 0.759 Fv = 1.500 SDS = 1.645

REINFORCED CONCRETE RESERVOIR

- Ri = 2.0
- Rc = 1.0
- le = 1.5
- Sai = 1.234
- Sac = 0.0195

SOIL DESIGN PARAMETERS:

- ASSUMED SOIL DESIGN PARAMETERS (CLASS 4 SOIL PER CBC 2019 TABLE 1806.2):
- ALLOWABLE SOIL BEARING = 2000 PSF (MAY BE INCREASED BY 1/3 FOR TRANSIENT LOADING CONDITIONS)
- SOIL FRICTION COEFFICIENT = 0.35 BETWEEN CRUSHED ROCK AGGREGATE BASE (CLASS 3 PER CBC 2019 1806.2) - SOIL SURFACE
- ACTIVE SOIL LATERAL PRESSURE = 45 PSF/FT (ASCE7-16 TABLE 3.2-1 SOIL TYPE GC)
- AT-REST SOIL LATERAL PRESSURE = 80 PSF/FT (ASCE7-16 TABLE 3.2-1 FOOTNOTE B)
- SEISMIC SOIL LATERAL PRESSURE = 30.5 PSF/FT (ASSUMED UNIFORMLY DISTRIBUTED LOAD)
- PASSIVE SOIL LATERAL PRESSURE = 150 PSF/FT



TETRA TECH
www.tetratech.com
160 East Via Verde, Suite 200
San Dimas, California, 91773
Phone: (909) 305-2930 Fax: (909) 305-2959



5/16/25



MARK	DATE	DESCRIPTION	BY

MONTECITO WATER DISTRICT

RESERVOIR SEISMIC RETROFIT AND REPLACEMENT PROJECT FOR TERMINAL RESERVOIR

GENERAL STRUCTURAL NOTES

Project No.: 200-106490-21001


Designed By: GH

Drawn By: E.J.H

Checked By: VMR

S-001

5/15/2025 6:05:44 PM - O:\PROJECTS\IRVINE\106490\200-106490-21001\CAD\SHEETFILES\TERMINALS-S-101-DEMOP\DWG - HEINEN, GEOFF



KEYNOTES:

1. REMOVE AND DISPOSE OF EXISTING STEEL ROOF JOISTS
2. REMOVE AND REPLACE EXISTING OVERFLOW PIPE PER SHEET C-101.
3. EXISTING CONCRETE MASONRY WALL (PROTECT IN PLACE).
4. REMOVE AND DISPOSE OF EXISTING STEEL COLUMN AND BASE PLATE.
5. REMOVE AND DISPOSE OF EXISTING STEEL GIRDERS.
6. REMOVE AND DISPOSE OF EXISTING ACCESS HATCH
7. REMOVE AND DISPOSE OF EXISTING ROOFING PANELS
8. REMOVE AND DISPOSE OF EXISTING STEEL KNEE BRACES AT THE ROOF JOIST ALONG THE EAST AND WEST WALLS
9. CUT EXISTING COLUMN FOOTING AND CAST-IN-PLACE ANCHORS TO BE FLUSHED WITH TOP SURFACE OF EXISTING GUNITE OVERLAY.
10. REMOVE AND DISPOSE EXISTING EAVE VENTS
11. REMOVE AND DISPOSE EXISTING RIDGE VENT
12. REMOVE EXISTING CONCRETE CONCRETE SPILLWAY STRUCTURE WITH STEEL PLATE COVER
13. EXISTING 3" THICK GUNITE OVERLAY (PROTECT-IN-PLACE, UNLESS NOTED OTHERWISE).
14. REMOVE AND DISPOSE EXISTING CONCRETE STAIRWAY AND LANDING. TO BE FLUSHED WITH TOP SURFACE OF EXISTING GUNITE OVERLAY.
15. REMOVE AND DISPOSE OF EXISTING CONCRETE SLAB FOR THE SODIUM HYPOCHLORITE TANKS.

DEMOLITION PLAN


SCALE: 3/32"=1'-0"



TETRA TECH

www.tetrattech.com

160 East Via Verde, Suite 200
San Dimas, California, 91773
Phone: (909) 305-2930 Fax: (909) 305-2959



5/16/25



MARK	DATE	DESCRIPTION	BY

MONTECITO WATER DISTRICT
RESERVOIR SEISMIC RETROFIT AND REPLACEMENT
PROJECT FOR TERMINAL RESERVOIR


DEMOLITION PLAN

Project No.: 200-106490-21001
Designed By: VMR
Drawn By: EJJ
Checked By: VMR

S-101

Bar Measures 1 inch

5/15/2025 6:07:43 PM - O:\PROJECTS\IRVINE\106490\200-106490-21001\CAD\SHEETFILES\TERMINALS-102-FOUNDATION.DWG - HEINEN, GEOFF



- NOTE:
- CONCRETE OVERLAY SHALL BE MOIST CURED FOR AT LEAST SEVEN DAYS. THE CONCRETE SHALL BE COVERED WITH POLYETHYLENE SHEETS AND KEPT MOIST USING FOG NOZZLES FOR THE ENTIRE CURING PERIOD.
 - CONTRACTOR SHALL PERFORM A SURVEY AND FIELD VERIFY ALL NEW CONCRETE SURFACE ELEVATIONS PER THIS SHEET.

DATUM
DATUM (0'-0") IS AT THE FINISHED FLOOR AT THE NORTH EAST CORNER OF THE EXISTING RESERVOIR FLOOR SLAB AND IS AT ELEVATION 846.55

TETRA TECH
www.tetrattech.com
160 East Via Verde, Suite 200
San Dimas, California, 91773
Phone: (909) 305-2930 Fax: (909) 305-2959

REGISTERED PROFESSIONAL ENGINEER
WANTONG ERIC
No. 6177
STRUCTURAL
STATE OF CALIFORNIA
5/16/25

MONTECITO WATER DISTRICT

MARK	DATE	DESCRIPTION	BY

MONTECITO WATER DISTRICT
RESERVOIR SEISMIC RETROFIT AND REPLACEMENT
PROJECT FOR TERMINAL RESERVOIR


FOUNDATION PLAN

Project No.: 200-106490-21001
Designed By: VMR
Drawn By: EJJ
Checked By: VMR

S-102

Bar Measures 1 inch


5/15/2025 6:09:05 PM - C:\PROJECTS\IRVINE\106490\200-106490-21001\CAD\SHEET\TERMINALS-103-ROOF.DWG - HEINEN, GEOFF



ROOF SLAB PLACEMENT NOTES:

- ROOF SLAB SECTION SHALL BE DEFINED AS DIVIDED BY THE CONSTRUCTION JOINT AS SHOWN ON THIS DRAWING
- ROOF SLAB SECTIONS SHALL NOT BE CAST AGAINST OTHER CONCRETE PILE CAP SECTIONS UNTIL A MINIMUM OF 3 FULL DAYS (72 HOURS) HAS ELAPSED SINCE THE PREVIOUS SECTION WAS PLACED AND FINISHED.
- ROOF SLAB SHALL BE KEPT MOIST DURING FINISHING PERIOD BY USE OF A FOG NOZZLE. DURING CURING PERIOD, PILE CAP SHALL BE KEPT MOIST AND COVERED WITH POLYETHYLENE SHEETS. PILE CAP SHALL BE CURED FOR A PERIOD OF NOT LESS THAN SEVEN DAYS.

DATUM
DATUM (0'-0") IS AT THE FINISHED FLOOR
AT THE NORTH EAST CORNER OF
EXISTING RESERVOIR FLOOR SLAB AND
IS AT ELEVATION 846.55



TETRA TECH

www.tetratech.com

160 East Via Verde, Suite 200
San Dimas, California, 91773
Phone: (909) 305-2930 Fax: (909) 305-2959



MARK	DATE	DESCRIPTION	BY

MONTECITO WATER DISTRICT
RESERVOIR SEISMIC RETROFIT AND REPLACEMENT
PROJECT FOR TERMINAL RESERVOIR


ROOF DECK PLAN

Project No.: 200-106490-21001
Designed By: VMR
Drawn By: E.J.H.
Checked By: VMR


S-103

Bar Measures 1 inch

5/15/2025 6:10:27 PM - C:\PROJECTS\IRVINE\106490\200-106490-21001\CAD\SHEET\TERMINALS-S-301-WALL\SECTION.DWG - HEINEN, GEOFF




DATUM
DATUM (0'-0") IS AT THE FINISHED FLOOR
AT THE NORTH EAST CORNER OF THE
EXISTING RESERVOIR FLOOR SLAB AND
IS AT ELEVATION 846.55



TETRA TECH

www.tetrattech.com

160 East Via Verde, Suite 200
San Dimas, California, 91773
Phone: (909) 305-2930 Fax: (909) 305-2959



MARK	DATE	DESCRIPTION	BY

MONTECITO WATER DISTRICT
RESERVOIR SEISMIC RETROFIT AND REPLACEMENT
PROJECT FOR TERMINAL RESERVOIR


WALL RETROFIT SECTION

Project No.: 200-106490-21001
Designed By: GH
Drawn By: EJJ
Checked By: VMR


S-301

Bar Measures 1 inch


5/15/2025 6:11:33 PM - O:\PROJECTS\IRVINE\106490\200-106490-21001\CAD\SHEET\TERMINALS-302-SECTION.DWG - HEINEN, GEOFF



B TYPICAL MIDDLE STRIP SECTION
SCALE: 3/8"=1'-0"




C TYPICAL COLUMN STRIP SECTION
SCALE: 3/8"=1'-0"



TETRA TECH

www.tetrattech.com

160 East Via Verde, Suite 240
San Dimas, California, 91773
Phone: (909) 305-2930 Fax: (909) 305-2959



4/18/25



MARK	DATE	DESCRIPTION	BY


MONTECITO WATER DISTRICT
RESERVOIR SEISMIC RETROFIT AND REPLACEMENT
PROJECT FOR PARK LANE RESERVOIR

ROOF SLAB CROSS SECTION

Project No.: 200-106490-21001
Designed By: VMR
Drawn By: EJJ
Checked By: VMR

S-302

Bar Measures 1 inch




1 TYPICAL BAR BENDS
SCALE: N.T.S.

REINFORCING LAP SPLICE SCHEDULE					
BAR	f _c =2500	f _c =3250	f _c =4000	f _c =4500	f _c =5000
	L (inches)	L (inches)	L (inches)	L (inches)	L (inches)
3	24	21	19	18	17
4	32	28	25	24	23
5	39	35	31	30	28
6	47	42	37	35	34
7	69	60	54	51	49
8	78	69	62	59	56


- NOTES:
- LAPS SHOWN IN THIS TABLE ARE CLASS B, CATEGORY 3 TYPE SPLICES. LAP LENGTH IS BASED UPON SMALLER OF TWO BARS BEING SPLICED WHEN NOT THE SAME SIZE.
 - INCREASE LAP LENGTHS BY A FACTOR OF 1.3 FOR HORIZONTAL REINFORCEMENT SO PLACED THAT MORE THAN 12 INCHES OF CONCRETE IS CAST IN THE MEMBER BELOW THIS REINFORCEMENT.

2 REINFORCING LAP SPLICE SCHEDULE
SCALE: N.T.S.




- NOTE:
- ALL SPLICES SHALL BE MADE IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS. SUBMIT SHOP DRAWINGS PRIOR TO INSTALLATION OR SPLICING WATERSTOPS.
 - JOINTS AT CORNERS AND INTERSECTIONS OF WATERSTOPS SHALL BE SHOP FABRICATED (MITERED AND WELDED). BUTT SPLICES MAY BE MADE IN THE FIELD USING PERSONNEL, EQUIPMENT AND METHODS APPROVED BY THE WATERSTOP MANUFACTURER.


3 WATERSTOP DETAIL
SCALE: NTS




4 ADDITIONAL REINFORCING AT PENETRATIONS
SCALE: N.T.S.




5 TYPICAL ROOF SLAB OPENINGS
SCALE: N.T.S.




6 CONCRETE OVERLAY SLAB JOINT
SCALE: 1"=1'-0"




7 CONCRETE OVERLAY SLAB JOINT AT SLOPE CHANGE
SCALE: 1"=1'-0"




8 TYPICAL VERTICAL WALL JOINT
SCALE: 3/4" = 1'-0"



9 TYPICAL ROOF SLAB CONSTRUCTION JOINT
SCALE: 1"=1'-0"



10 TOP SLAB OVERLAY TO WALL JOINT
SCALE: 1 1/2"=1'-0"



11 CONCRETE THICKENED SLAB DETAIL
SCALE: 1"=1'-0"



160 East Via Verde, Suite 200
San Dimas, California, 91773
Phone: (909) 305-2930 Fax: (909) 305-2959



MARK	DATE	DESCRIPTION	BY

MONTECITO WATER DISTRICT
RESERVOIR SEISMIC RETROFIT AND REPLACEMENT
PROJECT FOR TERMINAL RESERVOIR


STRUCTURAL DETAILS 1

Project No.: 200-106490-21001
Designed By: GH
Drawn By: EJH
Checked By: VMR

S-501


Bar Measures 1 inch

5/15/2025 6:13:50 PM - O:\PROJECTS\IRVINE\106490\200-106490-21001\CAD\SHEETFILES\TERMINALS-S-502-DETAILS.DWG - HEINEN, GEOFF




1 TYPICAL LADDER DETAIL (SECTION)

SCALE: 3/4"=1'-0"




2 TYPICAL LADDER DETAIL (PLAN)

SCALE: 3/4"=1'-0"




3 LADDER DETAIL (ELEVATION)

SCALE: 3/4" = 1'-0"




4 LADDER BASE CONNECTION

SCALE: 3/4"=1'-0"




5 ROOF VENT OPENING

SCALE: 1"=1'-0"



6 ROOF SLAB CORNER REINF.

SCALE: 1"=1'-0"




7 HATCH CURB DETAIL

SCALE: 1"=1'-0"


8 NOT USED

SCALE:




9 MUD VALVE OPERATOR ACCESS HATCH

SCALE: 1 1/2"=1'-0"




10 NOT USED

SCALE:



11 NOT USED

SCALE:



12 NOT USED

SCALE:

TETRA TECH
www.tetrattech.com
160 East Via Verde, Suite 200
San Dimas, California, 91773
Phone: (909) 305-2930 Fax: (909) 305-2959

REGISTERED PROFESSIONAL ENGINEER
WANTONG ERIC
No. 6177
STRUCTURAL
STATE OF CALIFORNIA
5/16/25

MONTECITO WATER DISTRICT



MARK	DATE	DESCRIPTION	BY


MONTECITO WATER DISTRICT
RESERVOIR SEISMIC RETROFIT AND REPLACEMENT
PROJECT FOR TERMINAL RESERVOIR


STRUCTURAL DETAILS 2


Project No.: 200-106490-21001
Designed By: VMR
Drawn By: EJJ
Checked By: VMR

S-502



**TETRA TECH**
www.tetrattech.com
160 East Via Verde, Suite 200
San Dimas, California, 91773
Phone: (909) 305-2930 Fax: (909) 305-2959


5/16/25



MARK	DATE	DESCRIPTION	BY

MONTECITO WATER DISTRICT
RESERVOIR SEISMIC RETROFIT AND REPLACEMENT
PROJECT FOR TERMINAL RESERVOIR

STRUCTURAL DETAILS 3





Project No.: 200-106490-21001
Designed By: GH
Drawn By: EJJ
Checked By: VMR

S-503

5/15/2025 6:14:58 PM - O:\PROJECTS\IRVINE\106490-21001\CAD\SHEETFILES\TERMINALS-S-503-DETAILS.DWG - HEINEN, GEOFF

Consultant: Tetra Tech

Bar Measures 1 inch

[illegible]

MONTECITO WATER DISTRICT

RESERVOIR SEISMIC RETROFIT AND REPLACEMENT
PROJECT FOR TERMINAL RESERVOIR


STRUCTURAL DETAILS 4

Project No.:	200-106490-21001
Designed By:	GH
Drawn By:	EJH
Checked By:	YMB


S-504

5/15/2025 6:17:18 PM - O:\PROJECTS\IRVINE\106490\21001\CAD\SHEETFILES\TERMINALS-S-505-DETAILS.DWG - HEINEN, GEOFF


F
E
D
C
B
A



1 VAULT SECTION
SCALE: 1"=1'-0"



2 VAULT SECTION
SCALE: 1"=1'-0"



TETRA TECH

www.tetrattech.com
160 East Via Verde, Suite 200
San Dimas, California, 91773
Phone: (909) 305-2930 Fax: (909) 305-2959



MARK	DATE	DESCRIPTION	BY

MONTECITO WATER DISTRICT
RESERVOIR SEISMIC RETROFIT AND REPLACEMENT
PROJECT FOR TERMINAL RESERVOIR

STRUCTURAL DETAILS 5

Project No.: 200-106490-21001
Designed By: GH
Drawn By: EJJ
Checked By: VMR

S-505

Bar Measures 1 inch