

**MONTECITO WATER DISTRICT**

May 21, 2019

**ADDENDUM NO. 1**

TO REQUEST FOR PROPOSALS  
**Ashley Road Bridge Water Main Repair**

DATED MAY 2019

Notice is hereby given to bidders that this addendum is issued to make changes to the contract documents, construction drawings, and construction specifications. The following changes shall be made to the contract documents, construction drawings, and construction specifications by the Contractor.

**ADDENDUM 1-1: Q&A**

**Q:** Can the due date be extended?

**A:** Yes. The new bid due date is Monday May 27 at 5pm.

---

**Q:** What are the specifications of the concrete blocks to be used in the creek?

**A:** The District has four concrete blocks in their Yard that the Contractor can use on the project. These four blocks will satisfy the height requirement for securing the pipe above the creek. Contractor shall not include costs in their proposal for purchasing the concrete blocks.

---

**Q:** I noticed the existing bridge has a temporary main on it already. Is Phase 1 already completed?

**A:** No. Phase 1 is the relocation of the existing HDPE pipe to the north of the bridge. Contractor's proposals should include a lump sum cost for both Phase 1 and Phase 2 work.

---

**Q:** The County bridge detail shows the casing being 12" and installed 20 feet beyond the bridge deck – casing is too small and extension is too far – can you advise?

**A:** MWD has requested a 16" casing from the County and only 24" extension beyond the bridge deck. Contractor shall bid the job according to these two MWD requests.

---

**Q:** What are the specifications of the casing spacers and do you require end seals?

**A:** The casing spacers shall be Calpico Type PA/PE or engineer approved equivalent installed at 5 feet on center. Casing seals (2 total) shall be Calpico Type FW or engineer approved equivalent.

APPROVED:



---

Adam Kanold, P.E.  
Project Manager