

ADDENDUM 2: HOT SPRINGS ROAD WATER MAIN REPLACEMENT

MONTECITO WATER DISTRICT

January 15, 2021

ADDENDUM NO. 2

TO REQUEST FOR PROPOSALS
Hot Springs Road Water Main Replacement

DATED January, 2021

Notice is hereby given to bidders that this addendum is issued to make changes to the contract documents, construction drawings, and construction specifications. The following changes shall be made to the contract documents, construction drawings, and construction specifications by the Contractor.

ADDENDUM 2:

1. Q: At Sta. 13+00.00, it appears there is a new main line valve at the circle, but it's unclear, since no construction notes are provided. Can you please state what is required?

A: A gate valve is depicted at Sta. 13+00. The gate valve shall be a Mueller 8" resilient wedge gate valve with MJ x MJ connections.

2. Q: At Sta. 37+00.00, there is a new water service shown, but the call out has been cut off the page. Can you please state what size this service is?

A: The service line at station 37+00 shall be a 1" copper service line connection to a ¾" meter.

3. Q: Past Sta 42+27.78, you have a new 1" service and fire hydrant shown, but the line doesn't connect to the new main or old main. Is this an error?

A: The project will end at station 42+27.78. Anything depicted north of that will not be a part of this project.

APPROVED:



David Wong, E.I.T.
Engineering Assistant