

ADDENDUM 5: HOT SPRINGS ROAD WATER MAIN REPLACEMENT

MONTECITO WATER DISTRICT

January 20, 2021

ADDENDUM NO. 5

TO REQUEST FOR PROPOSALS
Hot Springs Road Water Main Replacement

DATED January, 2021

Notice is hereby given to bidders that this addendum is issued to make changes to the contract documents, construction drawings, and construction specifications. The following changes shall be made to the contract documents, construction drawings, and construction specifications by the Contractor.

ADDENDUM 5:


5-1: Change Section C1.02.13 to the following:

13. Fire Hydrant Assembly: The unit price paid per assembly shall include full compensation for furnishing all labor, materials, tools, equipment and incidentals for satisfactory installation of the fire hydrant assembly; complete in place and operable; in accordance with the design drawings. The fire hydrant assembly includes **all piping**, hydrant bury, concrete thrust block, breakaway spool, and new Jones fire hydrant. The old hydrant and spool shall be removed and disposed.

5-2: Q&A

- Q. The trench detail provided has conflicting dimensions. The top of the detail shows a minimum trench width of 18 inches while the dimension between the pipe and trench wall shows an "8" MIN. TYP.". For an 8" pipe install, the trench width would be 24 inches to satisfy the 8" minimum. Could you please clarify?
- A. The trench detail on sheet A419-7 does not specify the pipe size. Although the main line will be 8" and 12" the pipe sizes may be smaller at tie-ins, fire hydrants, and service laterals. Regardless of the pipe size, the minimum trench width is 18".

APPROVED:


David Wong, E.I.T.
Engineering Assistant