

ADDENDUM 6: HOT SPRINGS ROAD WATER MAIN REPLACEMENT

**MONTECITO WATER DISTRICT**

January 21, 2021

**ADDENDUM NO. 6**

TO REQUEST FOR PROPOSALS  
**Hot Springs Road Water Main Replacement**

DATED January, 2021

Notice is hereby given to bidders that this addendum is issued to make changes to the contract documents, construction drawings, and construction specifications. The following changes shall be made to the contract documents, construction drawings, and construction specifications by the Contractor.

**ADDENDUM 6:**

**Q:** There is a conflict between note 2 on Sheet A419-2 of the plans and Section C4.01 "Abandonment or Removal of Existing Water Mains and Appurtenances." Could you please clarify the extent of the abandonment?

**A:** Replace Note 2 on Sheet A419-2 and Section C4.01 "Abandonment or Removal of Existing Water Mains and Appurtenances" with the following"

"Existing water mains that are to be abandoned or are encountered in excavations for the new mains shall, to the extent feasible, remain in place, **and be capped with a DI mechanical joint endcap or concrete plug** and abandoned in place after all services have been connected to the new water mains. Abandonment of water mains shall include removal of any valve cans or appurtenances."

APPROVED:



David Wong, E.I.T.  
Engineering Assistant